

To: 1 000133 2-6
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App.
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15-033-20841-00-00 69
033-20,841
API NUMBER 15-
SW NW NE, SEC. 34, T. 34 S, R. 20 W/E
1150 feet from N section line
2575 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4145
Operator: Roberts & Murphy, Inc.
Name & Address: P.O. Box 7125
Shreveport, LA 71137-7125

Lease Name Miller Well # 4-34
County Comanche 211.25
Well Total Depth 6500 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 678

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Triad Drilling License Number 7345
Address 5400 N. Grand Blvd., Suite 310, Oklahoma City, OK 73112

Company to plug at: Hour: 10:15 p.m. Day: 5 Month: 2 Year: 19 92

Plugging proposal received from Lloyd Hubbard
(company name) Triad Drilling (phone) 405-948-6006

were: to fill hole with heavy mud and spot cement through drill pipe. Anhydrite 1000-1100'
1st plug at 1100' with 50 sx cement, 2nd plug at 700' with 50 sx cement,
3rd plug at 40' with 10 sx cement, 4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:15 a.m. Day: 6 Month: 2 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 1100' with 50 sx cement,
2nd plug at 700' with 50 sx cement,
3rd plug at 40' with 40 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Z-10-1992
COLLIER COUNTY
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel by Western.
(If additional description is necessary, use BACK of this form.)

I (XXX) did not observe this plugging.

INVOICED
DATE 3-5-92
INV. NO. 34679

Signed [Signature]
(TECHNICIAN)