

1090955

15-033-20942-00-00

8

TO: STATE CORPORATION COMMISSION 10-8

API NUMBER 15-033-20,942  
E2 SE NW SEC. 34, T 34 S, R 20 W

CONSERVATION DIVISION - PLUGGING SECTION 1700 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2630 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME MILLER WELL # 6-34

TECHNICIAN'S PLUGGING REPORT COUNTY COMANCHE 221.98

OPERATOR LICENSE # 4145 WELL TOTAL DEPTH 6830 FEET

OPERATOR: ROBERTS & MURPHY, INC PRODUCTION CSG: SIZE 4 1/2 " FEET 6515

NAME AND PO BOX 7125 SURFACE CASING: SIZE 8 5/8 " FEET 653'

ADDRESS SHREVEPORT, LA 71137-7125

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR PRATT WELL SERVICE LICENSE NUMBER 5893

ADDRESS PO BOX 847, PRATT, KS 67124

COMPANY TO PLUG AT: HOUR: 12:30 PM DAY: 08 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM KEN FRAZIER

(COMPANY NAME) PRATT WELL SERVICE (PHONE) 316-672-5901

WERE:

SET CIBP AT 6000' AND DUMP BAIL 2 SX CEMENT. CUT CASING AND PULL. PUMP FROM SURFACE  
50 SX CEMENT, 8% PLUG AND 100 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 1:30 PM DAY: 08 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT

SET CIBP AT 6000' WITH 2 SX CEMENT ON TOP.

1ST PLUG PUMP IN 8 5/8" CASING 3 HULLS, 10 GEL, 50 SX CEMENT, 10 GEL, 1 HULL AND 150 SX  
CEMENT. MAXIMUM PSI PRESSURE 500#. SHUT IN AT VACUUM.

REMARKS: 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 5334' OF 4 1/2" CASING.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED (TECHNICIAN) FORM CP-2/3

8bbt/hl-01

15-09-98  
6-0125