

11-8

4- 041428

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-193-20,372-0000

SE SE NW /4 SEC. 31, 10 S, 31 W
2970 feet from S section line
2970 feet from E section line

Operator license# 5011

Lease Moorhaus well #31-6

Operator: Viking Resources, Inc.

County Thomas

Address: 105 S. Braodway
Suite 1040
Wichita, Kansas 67202

Well total depth 4700 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 345 feet
w/200 sx.

152.75

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:30A.M. Day: 8 Month: November Year: 92

Plugging proposal received from: Terry Richardson

Company: Viking Resources, Inc. Phone: 913-625-4567

Were: 4 1/2" casing set @ 4202' w/175 sx. cement. Perf. 4125' - 4128'.
Anhy. Perf. 2558' w/350 sx. W.L.M. 4130'.
Order 300 sx. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 12:00P.M., Day: 8, Month: November, Year: 92

Actual plugging report: Hooked-up to 4 1/2" casing. Pumped in 275 sx.
60/40 pozmix with 1/4# flocele plus 500# hulls. Max. 500 P.S.I.
S.I.P. 300#. 8 5/8" surface pipe had cement circulated to surface
at completion.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did[X] / did not[] observe the plugging. Dennis L. Hamel

1-6-93

37120

11-8-92

(agent)

1-5-93
5152