

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 8996

Operator: Mid Continent Resources Inc. County Thomas

Name & Address Box 399

Garden City, Ks. 67846

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated was dual completion D 24791

Plugging Contractor Halliburton Services License Number

Address Ness City, Ks.

Company to plug at: Hour: Day: 12 Month: Feb. Year: 19 91

Plugging proposal received from Dean Ives

(company name) Mid Continent (phone)

were: 8 5/8 set at 327 w/ sks cwc 5 1/2 set at 5290 w/ 230sks PBD. O.H.

Perfs 5255 - 5285. D. V. tool 2528 cwc toc. 120' logged. O.H. arb.

Packer 5215. Parted at 2425 (fish). Order 300 sks 65/35 poz 10% gel

2% Dicel 500 lbs. hulls. Halliburton Cement co. Hensley Company water trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:35AM Day: 12 Month: Feb. Year: 19 91

ACTUAL PLUGGING REPORT Sq 5 1/2 casing w/300 sks cement blend w/500 lbs.

Hulls mixed into max psi 500 lbs. Close in psi 200 lbs. Plug complete. 8 5/8

will be filled after casing is cut off w/Redi-mix. As was expected the cement

top was found to have dropped 1400 in the 5 1/2. This was sq w/132 sks cement blend
w/500 lbs. hulls mixed in. The 8 5/8 annulus was filled w/5 bbl slurry

This well was dual comp w/o.h. arb. and KC perfs and it looks like now
maybe a hole in casing up high.

Remarks: (If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 3-15-91
INV. NO. 31181

[Signature]

Signed Carl Goodrow
(TECHNICIAN)

Carl Goodrow

RECEIVED
STATE CORPORATION COMMISSION

MAR 13 1991
3-13-91