

6 33150

8-25

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 063-21,218 -00-00

SE NW, SEC. 21, T 12 S, R 30 W/Ex

3300 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Ward Trust Well # 1-A

Operator: Pickrell Drilling Co. Inc.

County Gove 149.55

Name & Address 110 N. Market, Suite 205

Well Total Depth 4540 feet

Wichita, Ks. 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 278

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Company Tools License Number 5123

Address Above

Company to plug at: Hour: AM Day: 25 Month: August Year: 19 88

Plugging proposal received from

(company name) Pickrell Drilling (phone)

were: 8 5/8" set at 278' w/150 sks cwc. Circ. no less than 36 vis. mud with no

loss or gain. Order 190 sks 60/40 Poz 6% Gel 3% C C 8 5/8" wiper plug. Allied Cement Co.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4:45AM Day: 25 Month: August Year: 19 88

ACTUAL PLUGGING REPORT With drill pipe spot plugs at 2325' w/25 sks

1375' w/100 sks and Hulls

330' w/40 sks

15 sks in rathole

RECEIVED STATE CORPORATION COMMISSION SEP 16 1988 CONSERVATION DIVISION Wichita, Kansas

Remarks: Any 2309' - 2340'. Elevation 2842'.

(If additional description is necessary, use BACK of this form.)

INVOICED

(If not observe this plugging.)

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow

DATE 9-20-88

INV. NO. 22320