

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-193-20,409-0000

NWSESE SEC. 35, T. 10 S., R. 31 W7P

TECHNICIAN'S PLUGGING REPORT

990 feet from S section line

990 feet from E section line

Operator License # 5549

Lease Name Bloom Well # 1

Operator: CFA OIL CO.

County THOMAS 150.80

Name & Address P.O. Box. 1087

Well Total Depth 4640 feet

JUNCTION CITY, KANSAS

Conductor Pipe: Size _____ feet

66441

Surface Casing: Size 8 5/8 feet 368

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor R & C DRILLING License Number _____

Address HAYS, KANSAS

Company to plug at: Hour: PM Day: 5 Month: 7 Year: 19 86

Plugging proposal received from JOHN WISE

(company name) R & C DRILLING (phone) _____

were: 8 5/8 SET @ 368' w/ 175 SX. CIRC. HOLE w/ HEAVY MUD SPOT
CEMENT PLUGS w/ DRILL PIPE KEEP HOLE FULL OF HEAVY MUD
BETWEEN PLUGS & BALANCE PLUGS w/ MUD. ORDER 190 SX.
60/40 POZ. 6 3/4 GAL 3 3/4 CC

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:30 PM Day: 5 Month: 7 Year: 19 86

ACTUAL PLUGGING REPORT SPOT D.P. @ 2500' DISPLACE 25 SX. LAYDOWN D.P.
TO 1550' DISPLACE 100 SX. CMT. MIX. + 15X. HULLS. LAYDOWN D.P.
TO 400' DISPLACE 40 SX. CMT. MIX. LAYDOWN D.P. ADJUST
MUD LEVEL IN HOLE TO 40' FILL HOLE TO BASE OF CELLAR
w/ 10 SX. CMT. MIX. CIRCULATE 15 SX. CMT. MIX. IN RATHOLE
TO PLOW DEPTH w/ JOINT OF PIPE. PLUG COMPLETE.

Remarks: ELEV 2945 GL ANV 2491-2530
(If additional description is necessary, use BACK of this form.)

INVOICED
AUG - 6 1986

DATE _____

INV. NO. 14608

8-4-86

Signed Carl Goodrow
(TECHNICIAN)

7-30-86