

15-195-00498-00-00

State of Kansas



FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
OCT 23 1963

REC 23 1963
12-26-1963
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Bob Miller of Leo J. Dreiling & Sons Inc has this date requested permission to plug the following described well:
James Zeman
Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: James Zeman,

Complete Address: 206 Circle Drive, Hays, Kansas.

Lease Name: Jagger Well No. 1

Location: CNW-NE-NE Sec. 25 Twp. 12 Rge. (E) (W) 25

County Trego Total Depth 4650 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:

236' --8 5/8" Surface pipe, cement circulated with 135 Sx.

Circulate hole with heavy mud, set plug @ 600' and 20 Sx. cement.

"	"	220' with $\frac{1}{4}$ Sk. hulls & 20 Sx. cement.
"	"	40' with $\frac{1}{2}$ Sk. hulls & 10 Sx. cement.

Very truly yours,

M. L. Nichols