



15-063 - 20094-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 8 1971
CONSERVATION DIVISION
Wichita, Kansas
12-06-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dale Bucheister of John O. Farmer, Incorporated has this date requested permission to plug the following described well:

Mr. Bucheister guarantees payment of the plugging fee.

Operator's full Name: Herndon Drilling Company,

Complete Address: Box #489, Tulsa, Oklahoma.

Lease Name: Boone Well No. 1

Location: SW-SW-SE Sec. 4 Twp. 12 Rge. (E)(W) 26

County: Gove Total Depth 4200' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bucheister was instructed to plug the well as follows:

208'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 975'.

Circulate hole with heavy mud. Pull DP to 1100' and displace 110 Cu. Ft. cement thru DP. Pull DP to 215' and displace 30 Cu. Ft. Cement thru DP. Pull DP, set plug @ 40' with 1/2 sack hulls and 10 Cu. Ft. to bottom of cellar.

Very truly yours,

Conservation Division Agent