



15-063-00107-00-00

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
OCT 20 1964  
10-20-1964  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Clyde Merckle of D. R. Lauck Oil Co. Inc. has this date requested permission to plug the following described well:

Mr. Merckle guarantees payment of the plugging fee.

Operator's full Name: D. R. Lauck Oil Company, Incorporated,

Complete Address: 301 So. Broadway, Wichita, Kansas.

Lease Name: Graham Well No. 1

Location: CNE-NE Sec. 19 Twp. 12 Rge. (E) (W) 26

County Gove Total Depth 4660 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Merckle was instructed to plug the well as follows:

206' -- 8 5/8" Surface pipe, cement circulated with 160 Sx.

Circulate hole with heavy mud, set plug @ 540' and 20 Sx. cement.

"	"	190' with $\frac{1}{2}$ sk. hulls & 20 Sx. cement.
"	"	40' with $\frac{1}{2}$ sk. hulls & 10 Sx. cement.

Very truly yours,

*H. D. Nichols*

Conservation Division Agent