



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 18 1972
04-18-1072
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Tom Buffington of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Buffington guarantees payment of the plugging fee.

Operator's full Name: Winkle Oil Company,

Complete Address: 1016 Union Center, Wichita, Kansas.

Lease Name: Walz Well No. 1

Location: SE-SE-NE Sec. 34 Twp. 12 Rge. (E)(W) 26

County: Gove Total Depth 3863' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Buffington was instructed to plug the well as follows:

255'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 925'.

Circulate hole with heavy mud. Pull DP to 1150' and displace 110 Cu. Ft. cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

M. L. Nichols

Conservation Division Agent