



15-063-2036-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 28 1972

CONSERVATION DIVISION
Wichita, Kansas

09-28-1972

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. H Herb Mason of Dunne-Gardner Petroleum, Inc. has this date requested permission to plug the following described well:

Mr. Mason guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling, Inc., Petroleum Resources,

Complete Address: P. O. Box #18407, Wichita, Kansas.

Lease Name: Zimmerman Well No. C-1

Location: NW-NE-NW Sec. 34 Twp. 12 Rge. (E)(W) 27

County: Gove Total Depth 4550' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mason was instructed to plug the well as follows:

352'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 975'.

Circulate hole with heavy mud. Pull DP to 1200' and displace 110 Cu. Ft. cement thru DP. Pull DP to 370' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

W. L. Dickel
Conservation Division Agent