



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
10-16-1972
16 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Herb Mason of Dunne-Gardner Petroleum, Inc., has this date requested permission to plug the following described well:

Mr. Mason guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling and Petroleum Resources,

Complete Address: Box #18407, Wichita, Kansas.

Lease Name: Roberts Well No. 1

Location: NW-SW-NE Sec. 25 Twp. 12 Rge. (E)(W) 28

County: Gove Total Depth 4444' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mason was instructed to plug the well as follows:

325'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 825'.

Circulate hole with heavy mud. Pull DP to 1050' and displace 110 Cu. Ft. cement thru DP. Pull DP to 340' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

A. L. Nichols
Conservation Division Agent