



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
03-03-1970  
MAR 3 1970

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Doug Meyers of Barbara Oil Company, has this date requested permission to plug the following described well:

Mr. Meyers guarantees payment of the plugging fee.

Operator's full Name: Barbara Oil Company,

Complete Address: 509 Union Center Building, Wichita, Kansas.

Lease Name: Volbracht Well No. 1

Location: NW-NW Sec. 4 Twp. 12 Rge. (E)(W) 30

County: Gove Total Depth 4580' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Meyers was instructed to plug the well as follows:

288'--8 5/8" Surface casing, cement circulated with 200 Sx.

Circulate hole with heavy mud. Pull DP to 1450' and displace 100 Sx. cement thru DP. Pull DP to 310' and displace 25 Sx. cement thru DP. Pull DP, set bridge 240' with 2 rock bulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

*W. G. Nichols*  
Conservation Division Agent