

State of Kansas



15-063-20232-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1974
11-15-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jack Richardson of Slawson Drilling Co., Inc., has this date requested permission to plug the following described well:

Mr. Richardson guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Schoendaler Well No. A-1

Location: CNE-SW Sec. 28 Twp. 12 Rge. (E)(W) 30

County: Gove Total Depth 4476' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Richardson was instructed to plug the well as follows:

253'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1000'.

Circulate hole with heavy mud. Pull DP to 1225' and displace 110 Cu. Ft. cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

K. L. Nichols
Conservation Division Agent