

Notice: Fill out COMPLETELY  
and return to Conservation Division at  
the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

RECEIVED

FEB 12 2010

KCC WICHITA

Form CP-4  
March 2009

Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 30705  
Name: Younger Energy Company  
Address 1: 453 S. Webb Rd., Suite 100  
Address 2: \_\_\_\_\_  
City: Wichita State: KS Zip: 67207 + 1310  
Contact Person: Diane Rebstock  
Phone: (316) 681-2542  
Type of Well: (Check one) ☒ Oil Well ☐ Gas Well ☐ OG ☐ D&A ☐ Cathodic  
☐ Water Supply Well ☐ Other: \_\_\_\_\_ ☐ SWD Permit #: \_\_\_\_\_  
☐ ENHR Permit #: \_\_\_\_\_ ☐ Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No  
Producing Formation(s): List All (If needed attach another sheet)  
Tarkio Depth to Top: 2300 Bottom: 2365 T.D. 3165  
Topeka Depth to Top: 2571 Bottom: 2804 T.D. \_\_\_\_\_  
Lansing-K/C Depth to Top: 2871 Bottom: 3107 T.D. \_\_\_\_\_  
Reagan Sand 3130 3141

API No. 15 - 167-22,602-0000  
Spot Description: \_\_\_\_\_  
SE NE NE Sec. 36 Twp. 14 S. R. 14 ☐ East ☒ West  
4,290 Feet from ☐ North / ☒ South Line of Section  
330 Feet from ☒ East / ☐ West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
☐ NE ☐ NW ☒ SE ☐ SW  
County: Russell  
Lease Name: Julius Strecker Well #: 'B' 5  
Date Well Completed: August 26, 1985  
The plugging proposal was approved on: December 15, 2009 (Date)  
by: Bruce Bayse (KCC District Agent's Name)  
Plugging Commenced: December 15, 2009  
Plugging Completed: December 15, 2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Tarkio	Oil	surface	8-5/8"	331'	none
Topeka	Oil	production	5-1/2"	3163'	none
Lansing-K/C	Oil				
Reagan Sand	Oil				

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Stuck tool and parted sandline drill while attempting to knock out CIBP set at 2820'. Fished out the drill. KCC approved leaving the CIBP in place. Pumped 75 sxs cement at 2787'. Pumped 100 sxs cement at 2000'. Pumped 125 sxs cement at 1000'. Circulated cement out 5-1/2" and 8-5/8". Topped off casing with 25 sxs cement. Used total of 325 sxs 60/40 pozmix 4% gel.

Plugging Contractor License #: 7023 Name: Klima Well Service, Inc.  
Address 1: P.O. Box 48 Address 2: 908 Macarthur  
City: Great Bend State: KS Zip: 67530 + 0048  
Phone: (620) 793-8888  
Name of Party Responsible for Plugging Fees: Younger Energy Company  
State of Kansas County, Sedgwick, ss.  
Diane Rebstock ☒ Employee of Operator or ☐ Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Diane Rebstock, V.P. Finance.

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita,

