

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 34318 Name: Berexco LLC Address 1: PO Box 20380 Address 2: City: Wichita State: KS Zip: 67208 Contact Person: Evan Mayhew Phone: (316) 265-3311 Type of Well: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (if needed attach another sheet) Mississippi Depth to Top: 3645 Bottom: 3699 T.D. 3699

API No. 15 - 191-10113-0000 Spot Description: SW SE SW Sec. 33 Twp. 31 S. R. 1 East West 330 Feet from North South Line of Section 3,630 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Sumner Lease Name: Wellington Unit Well #: 85 Date Well Completed: 06 December, 1936 The plugging proposal was approved on: August, 2009 (Date) by: Steve VanGieson (KCC District Agent's Name) Plugging Commenced: 05 August, 2009 Plugging Completed: 06 August, 2009

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Rows include Mississippi oil, Surface 10", 329', none and Production 7", 3645', none.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Dumped 2 sacks common cement on top of Cast Iron Bridge Plug at 3600' with dump bailer. Set second cast iron bridge plug at 450'. Perforated 4 holes in 7" casing at 400'. Tied onto 7" casing, broke circulation. Pumped 200 sacks 60/40 POZ with 4% gel down 7" casing. Cement circulated to surface. Shut in surface casing, pumped 50 more sacks cement. After 30 minutes, pumped final 50 sacks cement, for a total of 300 sacks pumped. Left cement at surface inside casing. Cut casing off 3' below ground level. Witnessed by Steve VanGieson with KCC.

RECEIVED

FEB 16 2010

KCC WICHITA

Plugging Contractor License #: 34318-5363 Name: Berexco LLC Address 1: PO Box 20380 Address 2: City: Wichita State: KS Zip: 67208 Phone: (316) 265-3311

Name of Party Responsible for Plugging Fees: Berexco LLC State of KS County, Sedgwick, ss.

Richard R. Smith (Print Name) Employee of Operator or Operator on above-described well

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Richard R. Smith

COPELAND

Acid & Cement

BURRTON, KS GREAT BEND, KS
 (620) 463-5161 (620) 793-3366
 FAX (620) 463-2104 FAX (620) 793-3536

POST OFFICE BOX 438
 HAYSVILLE, KS 67060
 (316) 524-1225
 (316) 524-1027 FAX

Invoice

INVOICE NUMBER:
C33043-IN

BILL TO:
 BEREXCO, INC.
 P O BOX 723
 HAYS, KS 67601

WTF
HAYS RCVD.
AUG 14 2009

LEASE: WELLINGTON UNIT 85

AUG 17 2009

DATE	ORDER	SALESMAN	ORDER DATE	PURCHASE ORDER	SPECIAL INSTRUCTIONS	
08/13/2009	C33043		08/06/2009		NET 30	
QUANTITY	U/M	ITEM NO./DESCRIPTION		D/C	PRICE	EXTENSION
65.00	MI	CEMENT MILEAGE PUMP TRUCK		0.00	1.00	65.00
1.00	EA	CEMENT PUMP CHARGE		0.00	600.00	600.00
300.00	SAX	60-40 POZ MIX		0.00	9.25	2,775.00
6.00	SAX	2% ADDITIONAL GEL		0.00	16.00	96.00
306.00	EA	BULK CHARGE		0.00	1.25	382.50
874.90	MI	BULK TRUCK - TON MILES		0.00	1.10	962.39
REMIT TO: P.O. BOX 438 HAYSVILLE, KS 67060		COP		Net Invoice:		4,880.89
RECEIVED BY _____		FUEL SURCHARGE IS NOT TAXABLE AND IS ADDED TO MILEAGE, PUMP AND OR DELIVERY CHARGES ONLY.		SUMCO Sales Tax:		37.80
		NET 30 DAYS		Invoice Total:		<u>4,918.69</u>

RECEIVED
FEB 16 2010
KCC WICHITA

There will be a charge of 1.5% (18% annual rate) on all accounts over 30 days past due.

Copeland Acid & Cement is a subsidiary of Gressel Oil Field Service, Inc.

Gressel Oil Field Service, Inc. reserves a security interest in the goods sold until the same are paid for in full and reserve all the rights of a secured party under the Uniform Commercial Code



FIELD ORDER N° C 33043

BOX 438 • HAYSVILLE, KANSAS 67060
316-524-1225

DATE 8-6-09 20__

IS AUTHORIZED BY: Berexco (NAME OF CUSTOMER)

Address _____ City _____ State _____

To Treat Well As Follows: Lease Wellington Unit Well No. 85 Customer Order No. _____

Sec. Twp. Range _____ County Sevier State KS

CONDITIONS: As a part of the consideration hereof it is agreed that Copeland Acid Service is to service or treat at owners risk, the hereinbefore mentioned well and is not to be held liable for any damage that may accrue in connection with said service or treatment. Copeland Acid Service has made no representation, expressed or implied, and no representations have been relied on, as to what may be the results or effect of the servicing or treating said well. The consideration of said service or treatment is payable. There will be no discount allowed subsequent to such date. 6% interest will be charged after 60 days. Total charges are subject to correction by our invoicing department in accordance with latest published price schedules.

The undersigned represents himself to be duly authorized to sign this order for well owner or operator.

THIS ORDER MUST BE SIGNED BEFORE WORK IS COMMENCED _____ By _____ Agent

CODE	QUANTITY	DESCRIPTION	UNIT COST	AMOUNT
4101	65	Mileage Pickup	1.00	65.00
4100	1	Pump Charge		600.00
4100	3000	9% water. 2% sol.	9.25	2775.00
4050	6	2% add. sol.	16.00	96.00
4200	306	Bulk Charge	1.25	382.50
4201		Bulk Truck Miles $13.467 \times 65m = 874.97m \times 1.10$	1.10	962.37
		Process License Fee on _____ Gallons		
TOTAL BILLING				4880.87

I certify that the above material has been accepted and used; that the above service was performed in a good and workmanlike manner under the direction, supervision and control of the owner, operator or his agent, whose signature appears below.

Copeland Representative Nathan W.

Station G.O.

Jason
Well Owner, Operator or Agent

RECEIVED

Remarks _____

NET 30 DAYS

FEB 16 2010

KCC WICHITA



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

BEREXCO, INC.
PO BOX 20380
WICHITA, KS 67208-1380

July 09, 2009

Re: Wellington Unit #85
API 15-191-10113-00-00
33-31S-1W, 330 FSL 3630 FEL
SUMNER COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after January 5, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000

CONSERVATION DIVISION
Finney State Office Building, 130 S. Market, Room 2078, Wichita, KS 67202-3802
(316) 337-6200 • Fax (316) 337-6211 • <http://kcc.ks.gov/>

RECEIVED

FEB 16 2010

KCC WICHITA