

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 34318 Name: Berexco LLC Address 1: PO Box 20380 Address 2: Wichita State: KS Zip: 67208 Contact Person: Evan Mayhew Phone: (316) 265-3311 Type of Well: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (if needed attach another sheet) Mississippi Depth to Top: 3648 Bottom: 3696 T.D. 3696

API No. 15 - 191-19043-0000 Spot Description: NE, NW, SW Sec. 4 Twp. 32 S. R. 1 East West 2,128 Feet from North South Line of Section 3,991 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Sumner Lease Name: Wellington Unit Well #: 118 Date Well Completed: 18 August, 1946 The plugging proposal was approved on: August, 2009 by: Steve VanGieson (KCC District Agent's Name) Plugging Commenced: 05 August, 2009 Plugging Completed: 06 August, 2009

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Rows include Mississippi oil formation with Surface casing (10") and Production casing (5 1/2").

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Dumped 2 sacks common cement on top of Cast Iron Bridge Plug at 3600' with dump bailer. Set second cast iron bridge plug at 450'. Perforated 4 holes in 5 1/2" casing at 400'. Cut 4" window in surface casing. Tied onto 5 1/2" casing, broke circulation with water. Pumped 210 sacks 60/40 POZ with 4% gel down 5 1/2" casing. Cement circulated to surface. Cut both 10" and 5 1/2" casing off 3' below ground level and covered up.

RECEIVED FEB 16 2010

Plugging Contractor License #: 5363 Name: Berexco LLC Address 1: PO Box 20380 Address 2: Wichita State: KS Zip: 67208 Phone: (316) 265-3311

KCC WICHITA

Name of Party Responsible for Plugging Fees: Berexco LLC State of KS County, Sedgwick, ss. Richard R. Smith (Print Name) Employee of Operator or Operator on above-described well

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Richard R. Smith

COPELAND

Acid & Cement

OFFICE BOX 438
 HAYSVILLE, KS 67060
 (316) 524-1225
 (316) 524-1027 FAX

voice

BURRTON, KS GREAT BEND, KS
 (620) 463-5161 (620) 793-3366
 FAX (620) 463-2104 FAX (620) 793-3536

WF

CC

INVOICE NUMBER:
 C33042-IN

BILL TO:
 BEREXCO, INC.
 P O BOX 723
 HAYS, KS 67601

LEASE: WELLINGTON UNIT 118

HAYS RCVD.
 AUG 14 2009

AUG 17 2009

DATE	ORDER	SALESMAN	ORDER DATE	PURCHASE ORDER	SPECIAL INSTRUCTIONS	
08/13/2009	C33042		08/05/2009		NET 30	
QUANTITY	U/M	ITEM NO./DESCRIPTION		D/C	PRICE	EXTENSION
65.00	MI	CEMENT MILEAGE PUMP TRUCK		0.00	3.00	195.00
1.00	EA	CEMENT PUMP CHARGE		0.00	600.00	600.00
210.00	SAX	60-40 POZ MIX		0.00	9.25	1,942.50
5.00	SAX	2% ADDITIONAL GEL		0.00	16.00	80.00
215.00	EA	BULK CHARGE		0.00	1.25	268.75
614.90	MI	BULK TRUCK - TON MILES		0.00	1.10	676.39
EMIT TO: P.O. BOX 438 HAYSVILLE, KS 67060		COP		Net Invoice:		3,762.64
		FUEL SURCHARGE IS NOT TAXABLE AND IS ADDED TO MILEAGE, PUMP AND OR DELIVERY CHARGES ONLY.		ELICO Sales Tax:		31.80
RECEIVED BY		NET 30 DAYS		Invoice Total:		<u>3,794.44</u>

RECEIVED
 FEB 16 2010
 KCC WICHITA

There will be a charge of 1.5% (18% annual rate) on all accounts over 30 days past due.

LOG-TECH
 1013 240th Ave.
HAYS, KANSAS 67601
 (785) 625-3858

Copy 28514

Date 8-5-2009

CHARGE TO: BEREXCO
 ADDRESS _____
 R/A SOURCE NO. _____ CUSTOMER ORDER NO. OW 260
 LEASE AND WELL NO. Wellington Unit #18 FIELD _____
 NEAREST TOWN Wellington COUNTY Sumner STATE KS
 SPOT LOCATION _____ SEC. 4 TWP. 32 S RANGE 1 W
 ZERO G.L. CASING SIZE 5.5" WEIGHT _____
 CUSTOMER'S T.D. _____ LOG TECH _____ FLUID LEVEL _____
 ENGINEER D. Bradford - W. Bradford OPERATOR C. Bates


PERFORATING						
Description	No. Shots	Depth		Amount		
		From	To			
1 x 4 spf HEC	4	400	401	1100	00	

DEPTH AND OPERATIONS CHARGES					
Description	Depth		Total No. Ft.	Price Per Ft.	Amount
	From	To			
Dump 2 sacks Cement	0	3600	3600	.20	720 00

MISCELLANEOUS			
Description	Quantity	Amount	
Service Charge			
T.J.	Truck Rental #16		950 00
A.O.L.	Mast rental		500 00
S.J.			
F.J.	T.W.T.		

PRICES SUBJECT TO CORRECTION BY BILLING DEPARTMENT

RECEIVED THE ABOVE SERVICES ACCORDING TO THE TERMS AND CONDITIONS SPECIFIED ON THE REVERSE SIDE TO WHICH WE HEREBY AGREE.

Customer Signature 

Date 8-6-09

RECEIVED
 Sub Total 3270 00 VL
 FEB 16 2010 1150 00 KD
 Tax 72 45 8-10
KCC WICHITA
 \$ 1222.45