

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 823-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 6407  
Name: Flowers Production Co., Inc.  
Address 1: 622 Oil Hill Road  
Address 2: P.O. Box 249  
City: El Dorado State: KS Zip: 67042 +  
Contact Person: Dallas Flowers  
Phone: (316) 321-0550  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ~~Oil Well~~ Permit #: E-26697  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
Mississippi Depth to Top: 2732 Bottom: 2741 T.D. 2741  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 015-19348-00-00  
Spot Description: SE SW SE  
\_\_\_\_\_ Sec. 3 Twp. 25 S. R. 3  East  West  
347 Feet from  North /  South Line of Section  
1,700 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Butler  
Lease Name: Joseph Well #: 3  
Date Well Completed: 1-2-1954  
The plugging proposal was approved on: 3-26-09 (Date)  
by: Duane Krueger (KCC District Agent's Name)  
Plugging Commenced: 3-26-09  
Plugging Completed: 3-26-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Mississippi	oil & water	surface	15 1/2"	99'	0'
		production string	5 1/2"	2732	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RIH W/TBG @ 2,625' ESTABLISHED CIRCULATION, CONSOLIDATED OIL WELL SERVICE MIXED & PUMPED 50 SXS CLASS A 4% CC AND DISPLACED IN CASING. WAITED 2-HOURS, TAGGED CEMENT @ 2,072', TESTED CASING, HELD OK. RIH W/WIRELINE @250', AND SHOT SQUEEZE HOLES. DUG OUT CELLAR AND PLATED CASINGS TOGETHER. ESTABLISHED CIRCULATION, CONSOLIDATED MIXED & PUMPED 419 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED ON ALL STRINGS OF CASING. PLUG DOWN @ 8:00 P.M., 3-26-2009.

Plugging Contractor License #: 5870 Name: Phillips Well Service  
Address 1: P.O. Box 1263 Address 2: \_\_\_\_\_  
City: El Dorado State: KS Zip: 67042 +  
Phone: (316) 323-2160  
Name of Party Responsible for Plugging Fees: Flowers Production Co., Inc.  
State of Kansas County, Butler, ss.  
Dallas Flowers  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Dallas Flowers

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
FEB 16 2010  
KCC WICHITA