

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 33168  
Name: Woolsey Operating Company, LLC  
Address 1: 125 N Market Ste 1000  
Address 2: \_\_\_\_\_  
City: Wichita State: KS Zip: 67202 + 1729  
Contact Person: Carl W. Durr  
Phone: (620) 886-5606  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15-007-20666-00-01  
Spot Description: \_\_\_\_\_  
\_\_\_\_\_-NE SE Sec. 1 Twp. 32 S. R. 12  East  West  
1,980 Feet from  North /  South Line of Section  
660 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Barber  
Lease Name: Lukens OWWO Well #: 1  
Date Well Completed: \_\_\_\_\_  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: Steve Durrant (KCC District Agent's Name)  
Plugging Commenced: 02/01/10  
Plugging Completed: 02/03/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			8.625"	227'	
			4.50"	4,361'	3,020'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Blew gas off well. Pumped 20 sacks 200# hulls; Displaced with 62 bbls. of water. Tagged cement at 3,920'. Ripped casing at 3,260' and 3,020'. Pulled casing up to 600'; Pumped 10 gel wiper plug 50 sacks 3% cc 100# hulls. Pulled to 260'; Pumped 50 sacks 100# hulls. Pulled to 40'; Pumped 20 sacks to surface.

RECEIVED  
FEB 17 2010

Plugging Contractor License #: 31925 Name: Quality Well Service  
Address 1: 190th US 56 Highway Address 2: \_\_\_\_\_  
City: Ellinwood State: KS Zip: 67526 + \_\_\_\_\_  
Phone: (620) 727-3410

KCC WICHITA

Name of Party Responsible for Plugging Fees: Woolsey Operating Company, LLC  
State of Kansas County, Barber, ss.  
Carl W. Durr  Employee of Operator or  Operator on above-described well.  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Carl W. Durr



KANSAS CORPORATION COMMISSION 1032123  
OIL & GAS CONSERVATION DIVISION

Form CP-1  
March 2009

This Form must be Typed  
Form must be Signed  
All blanks must be Filled

**WELL PLUGGING APPLICATION**

Please TYPE Form and File ONE Copy

OPERATOR: License #: 33168  
Name: Woolsey Operating Company, LLC  
Address 1: 125 N MARKET STE 1000  
Address 2: \_\_\_\_\_  
City: WICHITA State: KS Zip: 67202 + 1729  
Contact Person: Carl W. Durr  
Phone: (620) 886-5606

API No. 15-007-20666-00-01  
If pre 1967, supply original completion date: \_\_\_\_\_  
Spot Description: \_\_\_\_\_  
\_\_\_\_ - NE-SE Sec. 1 Twp. 32 S. R. 12  East  West  
1,980 Feet from  North /  South Line of Section  
660 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Barber  
Lease Name: LUKENS Well #: 1 OWWO

Check One:  Oil Well  Gas Well  OG  D&A  Cathodic  Water Supply Well  Other: \_\_\_\_\_  
 SWD Permit #: \_\_\_\_\_  ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks  
Surface Casing Size: 8.625 Set at: 227 Cemented with: 185 Sacks  
Production Casing Size: 4.50 Set at: 4361 Cemented with: 160 Sacks

List (ALL) Perforations and Bridge Plug Sets:

Attached

*Sand back to 4200' + 45x. cement. If has gas pressure pump  
Bottom plug w/ 200# holls + 205x. cement.  
1st plug @ 600' w/ 10gal + 50 cent, 2nd plug @ 260 w/ 505x. cement.  
3rd plug @ 40' w/ 105x. cement. SP*

Elevation: 1479 ( G.L. /  K.B.) T.D.: 4654 PBTD: 4614 Anhydrite Depth: \_\_\_\_\_  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Junk in Hole  Casing Leak at: \_\_\_\_\_  
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

As per KCC recommendation

*pumped bottom 200# holls 205x cement Tagged cement @ 3920  
600 10gal 100# holls 505x 3%cc 260 505x 40' 205x.*

Is Well Log attached to this application?  Yes  No Is ACO-1 filed?  Yes  No

If ACO-1 not filed, explain why:

*pipe recovery 3020.*

RECEIVED

FEB 17 2010

KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Carl W. Durr  
Address: 1966 SE Rodeo Rd City: Medicine Lodge State: KS Zip: 67104 + \_\_\_\_\_  
Phone: (620) 886-5606  
Plugging Contractor License #: 31925 Name: Quality Well Service, Inc.  
Address 1: 190 US HWY 56 Address 2: \_\_\_\_\_  
City: ELLINWOOD State: KS Zip: 67526 + \_\_\_\_\_  
Phone: (620) 727-3410

Proposed Date of Plugging (if known): \_\_\_\_\_

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Submitted Electronically

# Quality Well Service, Inc.

190 US Highway 56  
Ellinwood, KS 67526

# Invoice

Date	Invoice #
2/8/2010	1151

Bill To
Woolsey Operating Company LLC 125 N Market, #1000 Wichita, KS 67202

P.O. No.	Terms	Lease Name
	Net	Lukens #1 OWWO

Description	Qty	Rate	Amount
Rig Time	20.5	185.00	3,792.50T
Floor Rental	1	125.00	125.00T
Shots	2	300.00	600.00T
Torch	1	50.00	50.00T
Water Truck	5.5	75.00	412.50T
Backhoe	5	75.00	375.00T
Out of Town	2	120.00	240.00T
Phone Calls	1	15.00	15.00T
Clerical	1	20.00	20.00T
Wiping Rubber	1	20.00	20.00T
Fresh Water	2	20.00	40.00T
02/01/10:  Drove to location and raised pole. Blew gas off well; Checked hole. Drove to motel.			
02/02/10:  Drove to location. Pumped 20 sacks 200# hulls; Displaced with 62 bbls of water. Dug cellar & pit; Unpacked casing head. St floor; Pulled slips. Checked bottom; Tagged cement at 3,920'. Ripped casing at 3,260' and 3,020'; Pipe came free. Swedge in; Drove to motel.			
02/03/10:  Drove to location. Pulled casing up to 600'; Pumped 10 gel wiper plug and 50 sacks 3% cc 100# hulls. Pulled to 260'; Pumped 50 sacks 100# hulls. Pulled to 40'; Pumped 20 sacks to surface. Tore down floor and rig. Emptied pit; Cleaned up location.			
<b>Subtotal</b>			\$5,690.00
<b>Sales Tax (6.3%)</b>			\$358.47
<b>Total</b>			\$6,048.47

RECEIVED  
FEB 17 2010  
KCC WICHITA