

STATE OF KANSAS
TATE CORPORATION COMMISSION
30 S. Market, Room 2078
Wichita, KS 67202

K.A.R.-82-3-117

API NUMBER 15-073-01067-0000

LEASE NAME Schultz

WELL NUMBER S-3
300 SE SE SW Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 31 TWP. 23 RGE. 12 (E) or (W)

COUNTY Greenwood

Date Well Completed 12-3-57

Plugging Commenced 11-12-07

Plugging Completed 11-19-07

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

COX, WILLIAM P. & LISA A. dba

LEASE OPERATOR A B & L Oil

ADDRESS 2357 N 5th St Madison KS 66860

PHONE(S) (620) 437-0246 OPERATORS LICENSE NO. 322916

Character of Well

Oil, Gas, D&A, SPO, Input, Water Supply Well

The plugging proposal was approved on 11-12-07 (date)

by Mike Hoffman (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation Bartlesville Depth to Top 1772 Bottom 1782 T.D. 1818

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out	RECEIVED
	Surface	0	100	10"	100'	0	MAY 17 2010
	Drill Casing	0	1883	7"	1883	0	
							KCC WICHITA

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section.

10 Sacks at 1710 Through Tubing Shot Hole in casing at 1710 plugged
20 Sack Through Tubing Shot Hole at 450' 99 Sack Through Tubing

Name of Plugging Contractor N F Snyder Co LLC License No. 32147

Address PO BOX 107 Hamilton KS 66853

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: B & L Oil

STATE OF KS COUNTY OF Greenwood, ss.

(Employee of Operator) or (Operator)
I, William P. Cox, being first duly sworn on oath, says: That I have knowledge of the fact
statements, and matters herein contained and the log of the above-described well as filed th
the same are true and correct, so help me God.

(Signature) William P. Cox


(Address) 2357 N 5th St Madison KS 66860

SUBSCRIBED AND SWORN TO before me this 21st day of April, 2010

Marcie A Harrison

Notary Public

My Commission Expires: 1/25/13



Form CP-4
Revised 05-08

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- **BERT YOUNG**
 Farm- **Schultz**

No. **3**

SEC. **31** T. **23** R. **12E**
SE SE SW

Total Depth. **1842'**
 Comm. **11-28-57** Comp. **12-3-57**
 Shot or Treated.
 Contractor. **Sunflower Drilling Company**
 Issued. **2-22-58**

County **Greenwood**
KANSAS



CASING:
 10 3/4" 100' cem w/50 sx
 7 " 1838' cem w/100 sx

Elevation. _____

Production. **20 BOPD**

Figures indicate Bottom of Formations.

soil	1
clay	10
shale	125
lime	140
lime & shale	245
shale & shell	275
lime	290
shale & shell	300
lime	305
shale & shells	365
lime	370
shale & shell	390
lime	425
shale & shells	750
lime Kansas City	920
shale & shells	930
lime	1210
shale & shells	1335
lime	1350
shale & shell	1361
lime	1387
shale & shell	1458
lime & shale	1580
shale & shells	1655
sand w/oil Cattleman	1659
shale & shells	1768
sand w/oil Bartlesville	1772
shale & shells	1834
Mississippi Chat	1841-RKB
Mississippi Chat	1842
Total Depth	

TOPS: SCOUT	
Kansas City	920
Cattleman	1659
Bartlesville	1772
Mississippi	1841

RECEIVED
MAY 17 2010
KCC WICHITA