

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
March 2009
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

OPERATOR: License #: 32457
 Name: ABERCROMBIE ENERGY, LLC
 Address 1: 150 N. MAIN, SUITE 801
 Address 2: _____
 City: WICHITA State: KS Zip: 67202 + 1 3 1 6
 Contact Person: GARY MISAK
 Phone: (316) 262-1841
 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (if needed attach another sheet)
L-KC 'K' Depth to Top: 4170 Bottom: 4174 T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 101-20,480 -0000
 Spot Description: _____
NW NW NW Sec. 9 Twp. 17 S. R. 27 East West
330 Feet from North / South Line of Section
330 Feet from East / West Line of Section
 Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
 County: LANE
 Lease Name: HOWARD Well #: 4
 Date Well Completed: 09-25-1980
 The plugging proposal was approved on: 11/4/2009 (Date)
 by: _____ (KCC District Agent's Name)
 Plugging Commenced: 11-12-09
 Plugging Completed: 11-18-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
L-KC	OIL/WTR.	SURFACE	8 5/8"	283'	NONE
		PRODUCTION	4 1/2"	4301'	NONE

**RECEIVED
FEB 22 2010
KCC WICHITA**

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Backed rods off @ 155 rods (3875' deep), backed off tbg. 119 jts. down (3862'), set CIBP @ 3840'. Located csg. leak between (1542-1878), dumped 2 sks cmt. on top of CIBP set @ 3840'. RIH w/tbg. and packer. Set packer @ 1350' and pumped 100 sks. cmt. w/300# hulls, pumped 100 sks. cmt. Pulled tbg. to 1100' and reverse circulated hole clean. Perf. @ 1000', 2 SPF, tagged cmt. @ 1095'. Hooked up to 4 1/2" and pumped 125 sks. cmt. w/100# hulls. Pumped 70 sks. cmt. down annulus between 4 1/2" and 8 5/8". Well plugged and abandoned.

Plugging Contractor License #: 32457 Name: Abercrombie Energy, LLC.
 Address 1: 150 N. Main, Suite 801 Address 2: _____
 City: Wichita State: KS Zip: 67202 + 1 3 1 6
 Phone: (316) 262-1841
 Name of Party Responsible for Plugging Fees: Abercrombie Energy, LLC.
 State of Kansas County, Sedgwick, ss.
Gary Misak Employee of Operator or Operator on above-described well
 (Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Gary Misak _____