

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 32457
Name: ABERCROMBIE ENERGY, LLC.
Address 1: 150 N MAIN, SUITE 801
Address 2: _____
City: WICHITA State: KS Zip: 67202 + 1 3 1 6
Contact Person: GARY MISAK
Phone: (316) 262-1841
Type of Well: (Check one) ☒ Oil Well ☐ Gas Well ☐ OG ☐ D&A ☐ Cathodic
☐ Water Supply Well ☐ Other: _____ ☐ SWD Permit #: _____
☐ ENHR Permit #: _____ ☐ Gas Storage Permit #: _____
Is ACO-1 filed? ☐ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No
Producing Formation(s): List All (if needed attach another sheet)
L-KC 'K' Depth to Top: 4155 Bottom: 4162 T.D. _____
L-KC 'L' Depth to Top: 4195 Bottom: 4205 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 101-20,444-0000
Spot Description: _____
SE NE NW Sec. 9 Twp. 17 S. R. 27 ☐ East ☒ West
990 Feet from ☒ North / ☐ South Line of Section
2390 2970 Feet from ☒ East / ☐ West Line of Section
Footages Calculated from Nearest Outside Section Corner:
☐ NE ☒ NW ☐ SE ☐ SW
County: LANE
Lease Name: HOWARD Well #: 3
Date Well Completed: 07-09-1980
The plugging proposal was approved on: 11/4/09 (Date)
by: _____ (KCC District Agent's Name)
Plugging Commenced: 11/19/09
Plugging Completed: 11/20/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
L-KC	OIL/WTR.	SURFACE	8 5/8"	285'	NONE
		PRODUCTON	4 1/2"	4317'	NONE

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Dumped 2 sks. cmt. on CIBP @ 3990'. Spotted 100 sks. cmt. and 100# hulls at 1600' thru tbq.
Perforated 1100' 2 SPF, tagged TOC @ 1345'. Pumped 150 sks. cmt. & 150# hulls down csg.
Pumped 50 sks. cmt. down 8 5/8" - 4 1/2" annulus.

RECEIVED

FEB 22 2010

KCC WICHITA

Plugging Contractor License #: 32382
32457 Name: SWIFT SERVICES
ABERCROMBIE ENERGY, LLC.
Address 1: 150 N. MAIN, SUITE 801 Address 2: _____
City: WICHITA State: KS Zip: 67202 + 1 3 1 6
Phone: (316) 262-1841
Name of Party Responsible for Plugging Fees: ABERCROMBIE ENERGY, LLC.
State of KANSAS County, SEDGWICK, ss.
GARY MISAK ☒ Employee of Operator or ☐ Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Gary Misak

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202