

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: N/A
Name: Frank Green (Landowner)
Address 1: P.O. Box 235
Address 2: _____
City: Chautauque State: KS Zip: 67334 + _____
Contact Person: Frank Green
Phone: (620) 216-0191
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
peru Depth to Top: 1060 Bottom: 1124 T.D. 1125'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 019-19708-00-00
Spot Description: _____
NW-SE-NE NW Sec. 11 Twp. 35 S. R. 11 East West
4334 Feet from North / South Line of Section
3195 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Chautauque
Lease Name: Springs Well #: 8
Date Well Completed: 1952'
The plugging proposal was approved on: 3-19-09 (Date)
by: Duane Sims (KCC District Agent's Name)
Plugging Commenced: 3-19-09 10:00 A.M.
Plugging Completed: 3-20-09 12:00 P.M.

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
<u>peru</u>		<u>production</u>	<u>4 1/2</u>	<u>HA</u>	<u>Ø</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

See attached statement # 8191

Plugging Contractor License #: 32884 Name: Elmore's Inc.
Address 1: P.O. Box 87 Address 2: _____
City: Sedan State: KS Zip: 67361 + _____
Phone: (620) 725-5744
Name of Party Responsible for Plugging Fees: No charge (Landowner Plugged well)
State of Kansas County, CO, ss.
FRANK GREEN Employee of Operator or Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the foregoing are true and correct, so help me God.
Signature: Frank Green

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 18 2010

ku

STATEMENT

8191

ELMORE'S INC.
 Box 87 - 776 HWY99
 Sedan, KS 67361
 Cell: (620) 249-2519
 Eve: (620) 725-5538

Date 3-19-09

RV Park

Customer Frank Green
 Address _____
 City _____ State _____ Zip _____

Qty.	Description	Price	Amount
2	hr Pulling Unit	95.00	190.00
2	hr Cement Pump	100.00	200.00
1	hr Water Truck	80.00	80.00
1	Bank Tank	80.00	80.00
2	Perforations (1 charge)	100.00	100.00
1	hr Backhoe	50.00	50.00
2	Sks Gel	15.00	30.00
222	Sks Cement	6.95	1542.00
			2272.00
	Springs #8 Plug Job	Tax	143.14
	Ran 1" IW To 1100'	\$	2415.14
	Gel Hole Spotted 5 Sks Cement		
	Plug Pulled 1" Out Perforated 4 1/2		
	Casing At 1050' + 350' Ran 1"		
	IW To 1050 Spotted 50' Cement Plug		
	Pulled Up To 350' Cemented To Surface		
	Inside + Outside Casing With 212 Sks		

Thank You -- We appreciate your business!
 Rec'd. by _____
 Cut off Surface Casing 3' Below Ground Restored Location

TERMS: Account due upon receipt of services. A 1 1/2% Service Charge, which is an annual percentage rate of 18% will be charged to accounts after 30 days.

pd #6268
 03-25-09

RECEIVED
 KANSAS CORPORATION COMMISSION
 FEB 18 2010
LEGAL SECTION