

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: R.P. Nixon Operations, Inc.  
Address: 207 West 12th Street  
Phone: (785) 628-3834 Operator License #: 5252  
Type of Well: oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 7/24/09 (Date)  
by: Steve Bond (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
Cherokee Sand Depth to Top: 4090' Bottom: 4093' T.D. \_\_\_\_\_  
Cherokee Sand Depth to Top: 4095' Bottom: 4098' T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-195-22361-0000  
Lease Name: Seibel D  
Well Number: 1  
Spot Location (QQQQ): Appr. - N/2 - N/2 - SW/4  
2310 Feet from  North /  South Section Line  
1254043 Feet from  East /  West Section Line  
Sec. 13 Twp. 14 S. R. 22  East  West  
County: Trego  
Date Well Completed: 9/13/06  
Plugging Commenced: 11/13/09  
Plugging Completed: 11/13/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	218'	none
				5 1/2"	4188'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 2" tubing to 4096'. Hooked up to tubing and pumped 12 sx of gel followed by 50 sx of 60/40 Pozmix, 4% gel with 150# of hulls. Pulled tubing to 1653' and pumped 180 sx of same cement to surface. Pulled tubing from well and tied onto casing. Topped well off with 20 sx of same cement. Tied on to backside of casing and pressured to 200#. Witnessed by KCC man Marvin Mills.

RECEIVED  
KANSAS CORPORATION COMMISSION

Name of Plugging Contractor: Express Well Service License #: 6426 MAY 25 2010  
Address: Highway 40 Victoria, KS 67671


Name of Party Responsible for Plugging Fees: R.P. Nixon Operations, Inc. CONSERVATION DIVISION WICHITA, KS

State of Kansas County, Ellis, ss.

Dan A. Nixon, Pres. of R.P. Nixon Oper., Inc. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 207 West 12th Street Hays, Ks 67601



and SWORN TO before me this 24th day of May, 20 10

[Signature] My Commission Expires: 3/12-2013  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten Signature]

# QUALITY OILWELL CEMENTING, INC.

Phone 785-483-2025  
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

No. 3890

Date	11-13-09	Sec.	13	Twp.	14	Range	22	County	TREGG	State	Ks	On Location		Finish	1:00 PM
Lease	SEIBEL	Well No.	D <sup>11</sup>		Location		CEDAR BLUFF								
Contractor	EXPRESS WELL SERVICE				Owner	I <sup>112</sup> N E 54 <sup>10</sup>									
Type Job	PTA				To Quality Oilwell Cementing, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.										
Hole Size	7 7/8		T.D.	4133											
Csg.	5 1/2 14"		Depth												
Tbg. Size	2 3/4		Depth	4094											
Tool			Depth												
Cement Left in Csg.			Shoe Joint	The above was done to satisfaction and supervision of owner agent or contractor.											
Meas Line			Displace	<b>CEMENT</b>											
<b>EQUIPMENT</b>				Amount Ordered	255 x 60/40 P2 4 1/2 GEL										
Pumptrk	5	No.	Cement Helper	JOE											
Bulktrk	2	No.	Driver	DOUG											
Bulktrk	PV	No.	Driver	TODD											
<b>JOB SERVICES &amp; REMARKS</b>				Common											
Remarks:				Poz. Mix											
1st Plug 4090'				Gel.											
5x GEL 50 x 60/40 P2 4 1/2 GEL W/ 150" h. flowseal				Calcium											
Disp H <sub>2</sub> O				Hulls	150"										
Pull tbg to 1050'				Salt											
Mix - Pump 180 x 60/40 P2 4 1/2 GEL				Handling											
CIRC OUT TO PIT				Mileage	.03 PER SEC PER MILE										
Hook up to Pump				<b>FLOAT EQUIPMENT</b>											
55x 60/40 P2 4 1/2 GEL				Guide Shoe											
175" Close In				Centralizer											
10' OFF W/ 2) x 60/40 P2 4 1/2 GEL				Baskets											
				AFU Inserts											
				RECEIVED KANSAS COMPTROLLER'S COMMISSION MAY 25 2010											
				CONTRACT NO. 3890											
14x GEL total				Guide Shoe											
255 x 60/40 P2 4 1/2 GEL total				Centralizer											
THANKS				Baskets											
TODD JOE DOUG				AFU Inserts											
Signature				Pumptrk Charge	PTA										
				Mileage	35										
				Tax											
				Discount											
				Total Charge											

PLEASE  
CALL  
AGAIN