

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: McCoy Petroleum Corporation

Address: 8080 E. Central, Suite #300, Wichita, KS 67206-2366

Phone: 316-636-2737 x 104 Operator License # 5003

Type of Well: Oil & Gas Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 11/1/09 (Date)

by: Jeff Klock (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Miss Depth to Top: 4244' Bottom: 4264' T.D. 4320' Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D.

API Number 15-095-21027

Lease Name: SWINGLE "T" #1-14

Well Number: #1-14

Spot Location (QQQQ): SE SW SE

330 Feet from North South Section Line

1650 Feet from East West Section Line

Sec 14 Twp 30 S. Rng. 9 East West

County: Kingman

Date Well Completed: 7/9/81

Plugging Commenced: 1/14/10

Plugging Completed: 1/18/10

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records, Casing Record (Surface Conductor & Production), Formation, Content, From, To, Size, Put In, Pulled Out. Includes data for 8 5/8" and 4 1/2" casing.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

1/18/10: Sand was at 4190'. Bailed 4 sacks cement with bailer. Cut surface off 4' below ground. Ripped casing at 2210' and 2035'. Pulled casing up to 1350' and pumped 35 sacks, 3% CC, 100# hulls. Tagged cement at 1210'. Pulled casing up to 900' and pumped 35 sacks cement. Pulled casing to 380' and pumped 120 sacks of cement to surface. Pulled rest of casing. Topped off 8 5/8" surface casing with 20 sacks cement. (All cement was 60/40 Pozmix with 4% Gel).

Name of Plugging Contractor: Quality Well Service License #: 31925

Address: 190th US 56 Highway, Ellinwood, KS 67526

Name of Party Responsible for Plugging Fees: McCoy Petroleum Corporation

State of Kansas County, Sedgwick, ss.

Scott Hampel - Employee of Operator (Employee of Operator) or (Operator) on above-described well, being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Scott Hampel

(Address) 8080 E. Central, Suite #300, Wichita, KS 67206-2366

BRENT B. REINHARDT Notary Public - State of Kansas My Appt. Expires 12/7/2011

SUBSCRIBED and SWORN TO before me this 3rd day of February 20 10

Brent B Reinhardt My Commission Expires: 12/7/2011 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202