

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: McCoy Petroleum Corporation

Address: 8080 E. Central, Suite #300, Wichita, KS 67206-2366

Phone: 316-636-2737 x 104 Operator License # 5003

Type of Well: Oil & Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 11/1/09 (Date)

by: Jeff Klock (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Miss _____ Depth to Top: 4199' Bottom: 4209' T.D. 4544'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number 15-095-30268 - 0000

Lease Name: SWINGLE "L" #2-12

Well Number: #2-12

Spot Location (QQQQ): S2 NE NW

4290 Feet from North / South Section Line

3300 Feet from East / West Section Line

Sec 12 Twp 30 S. Rng. 9 East West

County: Kingman

Date Well Completed: 11/17/66

Plugging Commenced: 1/18/10

Plugging Completed: 1/19/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	283'	None
				4 1/2"	4297'	2470'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1/19/10: Sand was at 4130'. Bailed 4 sacks cement with bailer. Cut surface off 4' below ground. Ripped casing at 2630' and 2470'.

Pulled casing up to 1350' and pumped 35 sacks, 3% CC, 100# hulls. Tagged cement at 1075'. Pulled casing up to 900' and pumped 35 sacks cement with 100# hulls. Pulled casing to 300' and pumped 100 sacks of cement to surface. Pulled rest of casing. (All cement was 60/40 Pozmix with 4% Gel).

Name of Plugging Contractor: Quality Well Service License #: 31925

Address: 190th US 56 Highway, Ellinwood, KS 67526

Name of Party Responsible for Plugging Fees: McCoy Petroleum Corporation

State of Kansas County, Sedgwick, ss.


RECEIVED

FEB 08 2010

KCC WICHITA

Scott Hampel - Employee of Operator

(Employee of Operator) or (Operator) on above-described well, being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Scott Hampel

(Address) 8080 E. Central, Suite #300, Wichita, KS 67206-2366

SUBSCRIBED and SWORN TO before me this 3rd day of February 20 10

Brent B Reinhardt My Commission Expires: 12/7/2011
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202