

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
March 2009
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

OPERATOR: License #: 6239
 Name: Zinszer Oil Company, Inc.
 Address 1: P.O. Box 211
 Address 2: _____
 City: Hays State: KS Zip: 67601 + _____
 Contact Person: Perry S. Henman
 Phone: (785) 625-9448
 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
none Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 083-21,612-00-00
 Spot Description: 50' north of,
NE SE NW Sec. 26 Twp. 22 S. R. 24 East West
1,600 Feet from North / South Line of Section
2,310 Feet from East / West Line of Section
 Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
 County: Hodgeman
 Lease Name: Springer Well #: 5
 Date Well Completed: 10/21/09
 The plugging proposal was approved on: 10/19/09 (Date)
 by: Steve Durrant (KCC District Agent's Name)
 Plugging Commenced: 2:15PM, 10/21/09
 Plugging Completed: 4:45PM, 10/21/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	223.40'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st plug @ 1620'W/50sx, 30sx in rat hole, circ 1st plug 15 minutes w/56 vis mud
 2nd plug @ 770'W/70sx, 20sx in mouse hole
 3rd plug @ 240'W/40sx
 4th plug @ 60'W/20sx, plugs displaced with mud, total 230sx 60/40poz, 4%gel, 1/4#CF/sx

**RECEIVED
FEB 11 2010
KCC WICHITA**


Plugging Contractor License #: 31548 Name: Discovery Drilling Co., Inc.
 Address 1: P.O. Box 763 Address 2: _____
 City: Hays State: KS Zip: 67601 + _____
 Phone: (785) 623-2920
 Name of Party Responsible for Plugging Fees: Zinszer Oil Company, Inc.

State of Kansas County, Ellis, ss.
Perry S. Henman (Print Name) Employee of Operator or Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Signature] Dated: 2-9-10
Cynthia A. Weigel - Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



[Handwritten initials]



Discovery Drilling

P.O. Box 763 • Hays, KS 67601 • OFFICE (785) 623-2920 • CELLULAR (785) 635-1511

DRILLER'S LOG

Operator: Zinszer Oil Co., Inc. LIC# 6239
PO Box 211
Hays, KS 67601

Contractor: Discovery Drilling Co., Inc. LIC#31548
PO Box 763
Hays, KS 67601

Lease: Springer #5

Location: 50'N of NE / SE / NW
Sec. 26 / 22S / 24W
Hodgeman Co., KS

Loggers Total Depth: 4650'
Rotary Total Depth: 4646'
Commenced: 10/13/2009
Casing: 8 5/8" @ 223.40' w / 150 sks

API#15- 083-21, 621-00-00
Elevation: 2384' GL / 2392' KB
Completed: 10/21/2009
Status: D & A

(All from KB)

Surface, Sand & Shale	0'	Shale	1636'
Dakota Sand	419'	Shale & Lime	2336'
Shale	495'	Shale	3097'
Cedar Hill Sand	1076'	Shale & Lime	3367'
Red Bed Shale	1275'	Lime & Shale	3979'
Anhydrite	1607'	RTD	4646'
Base Anhydrite	1636'		

STATE OF KANSAS)
) ss
COUNTY OF ELLIS)

Thomas H. Alm of Discovery Drilling states that to the best of his knowledge the above and foregoing is a true and correct log of the above captioned well.

Thomas H. Alm

Subscribed and sworn to before me on 10-23-09
My Commission expires: 8-9-11

(Place stamp or seal below)

Notary Public

RECEIVED
FEB 11 2010
KCC WICHITA

