

15-195-00173-00-00

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW-SW-SE

SEC. 15 TWP. 12 RGE. 23W

Dry Hole *** Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease ~~Spitznugle~~ Spitznugle

Operator Harms - Burt Drilling Co. Address Box 184. Great Bend, Kans.

Field _____ County Trego

Total Depth 3970' Feet.

(Describe briefly the manner in which the well was plugged)

Plugging Contractor. - Harms - Burt Drilling Company.

Plugging Contractor's License No. - _____

Address. - Box 184. Great Bend, Kansas.

Surface pipe - 8 5/8" set @ 190' c.w.c. 150 sx.

Filled hole with heavy mud to 185' from top, 1/2 sx. hulls, H.O.W.C.O. plug
and 20 sx. cem. through drill pipe. Mud to 40' from top, 1/2 sx. hulls,
H.O.W.C.O. plug and 10 sx. cem. to base of cellar.

RECEIVED
08-31-1954
CONSERVATION DIVISION
Wichita, Kansas
Wilton Lybrandt
District Conservation Agent

PLUGGING
FILE SEC 15 T 12 R 23w
BOOK PAGE 95 LINE 6

Date 8-29-56