

15-195-20252-00-00

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 5 1973
12-05-1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Rains & Williamson Oil Company, Incorporated,

Complete Address 435 Page Court, 220 West Douglas, Wichita, Kansas.

Lease Name Deines Well No. 1

Location NE Sec. 26 Twp. 12 Rge. (E) (W) 23
SW-NE-SE

County Trego Total Depth 4457'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Above

Address _____ License No. _____

Operation Completed: Hour 12:30 PM Day 1 Month 12 Year 1973

The above well was plugged as follows:

247'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 625'.

Circulated hole with heavy mud. Pulled DP to 850' and displaced 110 Cu. Ft. cement
thru DP from 850' to 525'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 12/10/73

INV. NO. 8273-W

Signed: A. L. Dehok
Well Plugging Supervisor