

15-195-20292-00-00



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
12-26-1974
DEC 26 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Beren Corporation
Complete Address 1130 Vickers KSB&T Bldg., Wichita, Kansas
Lease Name Donald Well No. 1
Location SW NW NE Sec. 22 Twp. 12 Rge. (E) (W) 23
County Trego Total Depth 3390'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Red Tiger Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 3:30 A Day 23 Month 12 Year 1974

The above well was plugged as follows:

RTD 3390' 8 5/8 csg set at 255' cwc 150 sx. Cem. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 800' thru drill pipe.
Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set
cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/3/75
INV. NO. 559-W

Signed: Luis F. Massey
Well Plugging Supervisor