

15-195-20231-00-00

Form CP-3
Rev. 6-4-68

KANSAS

2

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 11 1972
08-11-1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Mack Oil Company,

Complete Address 812 Union Center, Wichita, Kansas.

Lease Name Neff Well No. 1

Location CSW-SE Sec. 27 Twp. 12 Rge. (E) (W) 24

County Trego Total Depth 4540'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Thomas Drilling Company, Incorporated,

Address Box #100, Duncan, Oklahoma. License No.

Operation Completed: Hour 3:30 PM Day 8 Month 8 Year 1972

The above well was plugged as follows:

209'--8 5/5" Surface casing, cement circulated with 185 Sx.
Top of Dakota section @ 650'.

Circulated hole with heavy mud. Pulled DP to 875' and displaced 110 Cu. Ft. cement
thru DP from 875' to 550'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 110'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Fickel
Well Plugging Supervisor

INVOICED
DATE 8/11/72
INV. NO. 0156-W