

15-195-20139-00-20

Form CP-3  
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 24 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
10-24-1969

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name John O. Farmer, Incorporated,

Complete Address 370 West Wichita Avenue, Russell, Kansas.

Lease Name Pfeifer Well No. 1

Location SE-SE-NW Sec. 1 Twp. 12 Rge. (E) (W) 24

County Trego Total Depth 4072'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 2:30 PM Day 19 Month 10 Year 1969

The above well was plugged as follows:

194'--8 5/8" Surface casing, cement circulated with 140 Sx.  
Top of Dakota section @ 800'.

Circulated hole with heavy mud. Pulled DP to 1025' and displaced 100 Sx. cement thru  
DP. Pulled DP to 215' and displaced 20 Sx. cement thru DP from 215' to 155'. Pulled  
DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/27/69

INV. NO. 7234

Signed: M. L. Daniels  
Well Plugging Supervisor