

15-195-20365-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Trego County, Sec. 19 Twp. 12S Rge. 23W (E) (W)

Location as "NE/CNWxSWx" or footage from lines NE NE NW
Lease Owner Chief Drilling Co., Inc.
Lease Name Buchanan Well No. #1
Office Address 905 Century Plaza, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6/19/76 19
Application for plugging filed 6/28/76 19
Application for plugging approved 6/28/76 19
Plugging commenced 6/19/76 19
Plugging completed 6/19/76 19
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthzar
Producing formation Depth to top Bottom Total Depth of Well 4055 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	203'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged through drill pipe @ 850' w/70 sacks cement.
Plugged through drill pipe @ 200' w/20 sacks cement.
Plugged through drill pipe @ 40' w/10 sacks cement.

RECEIVED
JUN 20 1976
06-29-1974
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.
Address 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jim Robinson (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson
905 Century Plaza, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of June, 19 76

My commission expires

MARILYN SINARD
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY COMM. EXP. APR. 30, 1979

Marilyn Sinard
Marilyn Sinard
Notary Public.

WELL LOG

15-195-20365-00-00

CHIEF DRILLING CO., INC.
905 Century Plaza
Wichita, Kansas 67202

#1 BUCHANAN
NE NE NW Sec. 19-12S-23W
Trego County, Kansas

CONTRACTOR: Company Tools
CASING RECORD: 8 5/8" set @ 203' w/150 sx.

COMMENCED: 6/14/76
COMPLETED: 6/19/76

FORMATION	FROM	TO	ELEVATIONS
Sand & Surface Clay	0	130	2434 Gr.
Surface Clay, Sand & Shale	130	205	2436 D.F. 2439 K.B.
Shale & Surface Clay & Sand	205	1144	
Sand & Shale	1144	1933	
Anhydrite	1933	1975	
Shale	1975	3840	
Lime	3840	4055	
Total Depth	4055		

FORMATION TOPS	
Anhydrite	1933 + 506
Base Anhydrite	1975 + 464
Heebner	3766 - 1327
Toronto	3786 - 1347
Lansing	3801 - 1362
RTD	4055 - 1616

D & A

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the NE NE NW of Section 19, 12S-23W, Trego County, Kansas, to the best of my knowledge and belief.

RECEIVED
STATE COMMISSION
06-29-1976
JUN 29 1976
CONSERVATION DIVISION
Wichita, Kansas

CHIEF DRILLING CO., INC.
Jim Robinson
Jim Robinson, Vice-President

Subscribed and sworn to before me this 28th day of June, 1976.

MARILYN SINARD
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY COMM. EXP. APR. 30, 1979

Marilyn Sinard
Marilyn Sinard - Notary Public