

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Trego

County, Sec. 21 Twp. 12 Rge. 23 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NE NW

Lease Owner Wick Oil Company

Lease Name Wick Oil Co-Herman Bender Well No. 1

Office Address Wakeeney, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced Sept. 14 19 56

Plugging completed Oct. 2 19 56

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 4030 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 4030 feet to surface feet for each plug set.

Plug set at 3750 and ten foot of sand placed in hole followed by four sacks of cement placed in hole with dump bailer; hole filled with mud to 200 feet; ten foot rock bridge installed between 200 feet and 190 feet; twenty sacks of cement poured in hole and hole mudded to 35 foot; ten foot rock bridge installed between 30 and 20 feet; Ten sacks of cement poured in hole, forming cement cap to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes & Sons Pipe Pulling Company

Address Russell, Kansas

STATE OF Kansas, COUNTY OF Trego, ss.

W. E. Wickizer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *W. E. Wickizer*

Wakeeney, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 9th day of October, 1956

My commission expires Sept. 10, 1959

*Joy N. Horak*  
Notary Public.

PLUGGING  
FILE SEC 21 T. 12 R. 23W  
BOOK PAGE 98 LINE 10

RECEIVED  
OCT 10 1956  
10-10-1956  
CONS. DIV. STATE CORP. COM. DIVISION  
WICHITA, KANSAS

15-195-01409-00-00

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

Company- WICK PETROLEUM COMPANY  
Farm- Bender No. 1

SEC. 21 T. 12 R. 23W  
NE NE NW

Total Depth. 4037  
Comm. 3-28-53 Comp. 4-10-53  
Shot or Treated.  
Contractor.  
Issued. 11-28-53

County Trego  
KANSAS



CASING:  
8 5/8" 200'  
5" 4031'

Elevation. 2426

Production. Pmp 29 bbls in 8 hrs!

Figures indicate Bottom of Formations.

shale	630
shale, shells	1100
sand, shale	1600
shale	1705
red rock	1915
anhydrite	1957
shale, shells	2460
lime, shale	2725
lime	2880
shale, lime	3030
lime	3270
shale, lime	3645
lime	3570
shale, lime	3790
lime	4035 RTD
lime	4037
Total depth	

Tops: Geol.	
Anhydrite	1915
Topeka	3512
Heebner	3730
Toronto	3754
Lansing-Kansas city	3769
Marmaton	4026

DST #1 3798-3815 Open 1 hr. filled 30' oil.

DST #2 3814-31 Open 1 hr filled 34' watery mud.

DST #3 3910-35 Open 30 min. Filled 10' slightly oil cut mud.

DST #4 3935-75 Open 1 hr filled 15' mud.

Schlumberger run.

RECEIVED  
KANSAS GEOLOGICAL SOCIETY

SEP 12 1956  
09-12-1956  
KANSAS GEOLOGICAL SOCIETY

PLUGGING  
FILE SEC 21 T. 12 R. 23W  
BOOK PAGE 98 LINE 10