


15-195-00039-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Trego County. Sec. 21 Twp. 12 Rge. 23 (E) (W)
Location as "NE/CNW&SW&" or footage from lines NE NW SW
Lease Owner Permian Mud Service, Inc., et al
Lease Name Sheets Well No. #1
Office Address Box 1188, Odessa, Texas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed November 16 1952
Application for plugging filed November 16 1952
Application for plugging approved November 16 1952
Plugging commenced November 16 1952
Plugging completed November 17 1952
Reason for abandonment of well or producing formation dry hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Edon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4503 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	214'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

First plug set at 210' with 1/2 sack hulls and 15 sacks cement, hole filled with mud to 40', set second plug at 40' with 1/2 sack hulls and 10 sacks cement, cemented to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
NOV 22 1952
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Glenn R. Nye Drilling Company
Address Drawer 30, Hays, Kansas

STATE OF Kansas, COUNTY OF Ellis, ss.
Claude N. Bard (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Claude N. Bard
Plainville, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 21 day of November, 1952

John L. Spiss Notary Public.

My commission expires May 9, 1953

PLUGGING
FILE SEC 21 T 12 R 33
BOOK PAGE 60 LINE 2

15-195-00039-00-00

Company: Permian Mud Inc., et al
Contractor: Glenn R. Nye Drilling Company
Commenced: October 30, 1952
Completed: November 17, 1952

Farm: Sheets #1
Location: NE NW SW Sec. 21-12-23
Trego County, Kansas
Casing Record: 8 5/8" set at 214'
Elevation: 2421'
Dry and abandoned

(Figures below indicate bottoms)

cellar	5
surface soil & clay	45
sand & gravel	150
sand & shale	214
shale	614
shale	790
sand & shale	1150
shale & red bed	1280
shale & red bed	1380
sand & shale	1655
red bed & shale	1880
shale & red bed	1916
anhydrite	1955
shale & red bed	2180
shale & shells	2350
salt & shale	2380
lime & shale	2570
lime & shale	2700
lime & shale	2800
lime & shale	2885
lime & shale	2974
lime & shale	3075
lime & shale	3145
shale & lime	3200
lime & shale	3290
lime & shale	3405
lime & shale	3465
lime & shale	3550
lime & shale	3635
lime & shale	3679
lime & shale	3735
lime & shale	3798
lime & shale	3830
lime	3856
lime & shale	3873
lime	3881
lime	3912
lime	3920
lime	3952
lime	3987
shale & lime	3927
lime	4075
lime & shale	4119
lime & shale	4140
lime & shale	4180
lime & shale	4229
lime & shale	4265
lime & shale	4285
cherty lime & shale	4340
cherty lime	4385
lime	4423
cherty lime	4458
lime & shale	4465
lime	4495
arbuckle	4503

Top of arbuckle 4476
T. D.

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

PLUGGING
FILE SEC 21 T 12 R 232
BOOK PAGE 60 LINE 2

NOV 23 1952
11-22-1952
CONSERVATION DIVISION
Wichita, Kansas


15-195-00039-00-00

GLENN R. NYE DRILLING COMPANY

By Claude N. Bard

STATE OF KANSAS)
) SS
ELLIS COUNTY)

Subscribed and sworn to before me, a Notary Public, in and for said County and State this 21st day of Nov., 1952.



John L. Spiess
NOTARY PUBLIC

My Commission Expires, May 9, 1953

STATE OF KANSAS
COMMISSION
NOV 22 1952
REGISTRATION DIVISION
Wichita, Kansas