

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH

X			

Locate well correctly on above
Section Plat

Trego County. Sec 19 Twp 12 Rge 24 (E) W (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW/4 SW/4 NW/4
Lease Owner Prime Drilling Company, et al
Lease Name Howat Well No. 1
Office Address 3111 Apco Tower, Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-13-1951
Application for plugging filed 11-13-1951
Application for plugging approved 11-13-1951
Plugging commenced 11-13-1951
Plugging completed 11-13-1951
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 1118 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	253	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy drilling mud to 240', set plug cemented with 15 sacks cement & 1/2 sack Hulls, filled hole to 40' with heavy drilling mud set plug cemented to bottom of cellar with 10 sacks cement and 1-1/2 sacks Hulls.

11-17-1951

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Prime Drilling Company
Address 3111 Apco Tower, Oklahoma City, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.
L. J. Kruse (employee of owner) or (owner or operator)


being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. J. Kruse
Oklahoma City, Oklahoma (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of November, 1951.

My commission expires October 24, 1955

William Wright Notary Public



15-195-00204-00-00

PRIME DRILLING COMPANY, ET AL

HOWAT # 1 WELL

SW/4 SW/4 NW/4
 Sec. 19-12-24W
Trego County, Kans.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Rock & Sand	0	135	
Shale & Shells	135	249	8-5/8" C.S.A. @ 248'. Cemented with 150 Sacks Cement
Shale & Chalk Rock	249	350	
Shale & Shell	350	840	
Sand Pyrite	840	1025	
Shale & Shells	1025	1270	
Sand & Shale	1270	1340	
Shale & Sand	1340	1480	
Red Bed & Shale	1480	1660	
Sand Shale & Red Bed	1660	1835	
Red Bed & Shale	1835	2075	
Anhydrite	2075	2113	
Red Bed Shale Shells	2113	2285	
Red Bed & Shale	2285	2510	
Red Bed Shale & Lime	2510	2650	
Shale & Lime	2650	2670	
Red Bed, Shale & Lime	2670	2885	
Shale & Lime	2885	3065	
Lime	3065	3070	
Shale & Lime	3070	3150	
Lime & Shale	3150	3910	
Lime	3910	4060	
Lime & Shale	4060	4425	
Lime & Chert	4425	4448	
Total Depth		4448'	

I hereby certify the foregoing to be a true and accurate Driller's Log of the formations encountered in the above well.

PRIME DRILLING COMPANY

By: *L. J. Kruse*
 L. J. Kruse, Secretary

Subscribed and sworn to before me this 16th day of November, 1951.

Lillian Wright
 Notary Public 11-17-1951

My Commission Expires: October 24, 1955

FILE 19 12 740
 174 40