


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Trego County. Sec. 1 Twp. 12S Rge. 24W(E) (W)
Location as "NE/CNW&SW" or footage from lines NW NW NE
Lease Owner Imperial Oil of Kansas, Inc.
Lease Name Osborn "B" Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 12, 1956
Application for plugging filed May 12, 1956
Application for plugging approved May 12, 1956
Plugging commenced May 12, 1956
Plugging completed May 12, 1956
Reason for abandonment of well or producing formation No show of oil

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4593 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	5-12-56	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set No. 1 plug at 190 feet with
1/2 sack hulls and 15 sacks cement.
Set No. 2 plug at 40 feet with 1/2
sack hulls and 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1956
05-24-1956
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Imperial Oil of Kansas, Inc.
Address 903 Union National Bank Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Raymond L. Bacon (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.
(Signature) By: Raymond L. Bacon V-P
903 Union National Bank Bldg.
Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of May, 1956
My commission expires April 18, 1959
Frances E. Barham
Frances E. Barham Notary Public.

PLUGGING
FILE SEC. 1 T. 12 R. 24W
BOOK PAGE 63 LINE 8

15-195-00168-00-00

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
903 Union National Bank Building
Wichita 2, Kansas

Osborn "B" No. 1
NW NW NE Sec. 1-12S-24W
Trego County, Kansas

Total Depth: 4593'

Elevation: 2438' R.B.
Production: D & A

Commenced: 4-30-56 Completed: 5-12-56

Contractor: Imperial Oil of Kansas, Inc.
Wichita, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 203' with 175 sacks cement.

Figures indicate bottom of formations:

Surface Sand & Shale	202'		
Shale, Sand & Shells	530'		
Shale & Shells	930'		
Sand & Shale	1240'		
Shale, Sand & Shells	1890'		
Anhydrite	1935'	<u>TOPS</u>	
Shale & Shells	2060'	Anhydrite	1990' (/448)
Shale - Shells & Red Bed	2380'	Heebner	3767' (-1329)
Shale & Shells	2600'	Lansing	3803' (-1365)
Lime & Shale	3740'	Conglomerate	4336' (-1898)
Lime	4058'	Mississippi	4350' (-1912)
Lime & Shale	4190'	Viola	4448' (-2010)
Lime	4227'	Simpson	4526' (-2088)
Lime & Shale	4460'	Arbuckle	4546' (-2108)
Lime	4593'	Total Depth	4593' (-2155)
Total Depth	4593'		

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

PLUGGING			
FILE	SEC. 1	T. 12	R. 24W
BOOK	PAGE 63	LINE 8	

IMPERIAL OIL OF KANSAS, INC.

By: Ray G. Bacon
Vice-President

Subscribed and sworn to before me this 21st day of May, 1956.

RECEIVED
STATE COMMISSION
MAY 21 1956
05-24-1956
COMPTROLLER DIVISION
Wichita, Kansas

My Commission Expires:

April 18, 1959

Francis E. Barber
Notary Public