

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-195-22,101-00-00

LEASE NAME Fowler

WELL NUMBER 1

990 Ft. from S Section Line

1,650 Ft. from E Section Line

SEC. 4 TWP. 12S RGE. 24 COR. (W)

COUNTY Trego

Date Well Completed 12-8-91

Plugging Commenced 12-8-91

Plugging Completed 12-9-91

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR John O. Farmer, Inc.

ADDRESS Box 352, Russell, KS. 67665

PHONE#(913) 483-3144 OPERATORS LICENSE NO. 5135

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-27-91 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4,135'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	217'	Cmtd. w/140 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
Spot 25 sax cement @2,100' thru drill pipe. Spot 100 sax cement @1,155' thru drill pipe. Spot 40 sax cement @270' thru drill pipe. Push wiper plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole. Cement is 60-40 Pozmix w/6%

(If additional description is necessary, use BACK of this form.)  
jel and # flo-seal per sax. Plug down at 5:30 AM.

Name of Plugging Contractor Shields Drilling Co. License No. 164

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John O. Farmer, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. (Employee of Contractor or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts

statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec.-Treas.

(Address) Shields Bldg., Russell, KS.

SUBSCRIBED AND SWORN TO before me this 18th day of December, 19 91

Ruth Phillips  
Notary Public

My Commission Expires:



RECEIVED  
STATE CORPORATION COMMISSION

12-19-1991  
DEC 19 1991

CONSERVATION DIVISION



Shields


15-195-22101-00-00

Russell, Kansas

WELL LOG

Operator: John O. Farmer, Inc.  
Well: Fowler #1  
Commenced: December 2, 1991  
Completed: December 9, 1991  
Contractor: Shields Drilling Co.

Well Description: NE SW SE  
Sec. 4-12S-24W  
Trego Co., KS.



Elevation: 2,510' KB

Treatment:

Production: D & A

Tops:

CASING RECORD

Size	Run	Pulled
8 5/8"	217'	Cmtd. w/140 sax

..... Figures Indicate Bottom of Formations .....

Clay, shale & lime streaks	114'
Shale	692'
Shale & sand	1,355'
Shale	2,082'
Anhydrite	2,126'
Shale	3,066'
Shale & lime	3,873'
Lime	4,135' RTD

Notes

STATE COMMISSION

DEC 19 1991  
12-19-1991  
STATE COMMISSION