

API NUMBER 15-179-20593-0000

LEASE NAME Martin

WELL NUMBER 3

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

1980 Ft. from S Section Line

1650 Ft. from E Section Line  
 E/2 NW SE

SEC. 16 TWP. 10 RGE. 26W (E) or (W)

LEASE OPERATOR Petroleum Property Services, Inc.

ADDRESS 155 N. Market, #1010, Wichita, Kansas 67202-1824

COUNTY Sheridan

PHONE# (316) 265-3351 OPERATORS LICENSE NO. 31142

Date Well Completed \_\_\_\_\_

Character of Well Oil

Plugging Commenced 6-10-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-11-93

The plugging proposal was approved on \_\_\_\_\_ (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4075'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	244'	none
				4-1/2"	4037'	1121'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugged off bottom with sand to 3800' and 4 sacks cement. Shot pipe @2200', 1800', 1600', pumped 35 sacks cement @1600' to 2200'. Shot pipe @1330', 1121', pulled up to 975', pumped 65 sacks cement, pulled up to 300' and circulated 63 sacks cement to surface. Pulled rest of pipe and topped off with 15 sacks cement, 65/35 pos, 10% gel. Plugging Complete.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petroleum Property Services, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 15th day of June

Irene Herzberg  
 Notary Public

My Commission Expires: \_\_\_\_\_



RECEIVED  
 STATE CORPORATION COMMISSION  
 JUN 17 1993  
 6-17-93  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 Rev. 1-85-85-4  
 8-88-85-00