

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Sheridan County. Sec. 16 Twp. 10S Rge. 26 E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
NW SW NE

Lease Owner The Maurice L. Brown Co.
Lease Name MARTIN Well No. 1
Office Address 1500 Vickers KSB&T Bldg, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed August 27 1976
Application for plugging filed (verbally) August 27 1976
Application for plugging approved (verbally) August 27 1976
Plugging commenced August 27 1976
Plugging completed August 27 1976

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation Depth to top Bottom Total Depth of Well
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	249' K.B.	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st Plug set at 1100' with 70 sx.
2nd plug was set at 250' with 20 sx.
40' bridge with 10 sx.

RECEIVED
STATE CORPORATION COMMISSION

State Plugger: Gilbert Balthazor, Palco, Kansas

SEP 02 1976

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

STATE OF Kansas COUNTY OF Sedgwick ss.

Jerry A. Langrehr, Exec. V.P. (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerry A. Langrehr
801 Union Center, Wichita, Kansas 67202
(Address)

Subscribed AND SWORN to before me this 31st day of August 1976

July 21, 1979.

Sandra Richman Notary Public.



15-179-20430-0000

CONTRACTOR'S WELL LOG

OPERATOR: The Maurice L. Brown Co.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: MARTIN #1,
 LOCATION: NW SW NE, Section 16-10S-26W
 Sheridan County, Kansas
 SPUD DATE: August 17, 1976
 COMPLETION DATE: August 27, 1976

0	100	Surface Clay
100	160	Sand
160	1700	Shale
1700	1826	Shale & Sand
1826	1992	Sand
1992	2224	Shale
2224	2258	Anhydrite
2258	2950	Shale
2950	3230	Shale & Lime
3230	3340	Shale
3340	3505	Lime & Shale
3505	3605	Shale & Lime
3605	3820	Lime & Shale
3820	4115	Lime
	4115	Rotary Total Depth

Spud at 2:45 p.m., 8-17-76. Drilled 242' of 12 1/4" hole. Set 6 Jts. of 8 5/8" casing at 249' K.B. Set with 190 sx. of Class "A" cement, 3% Ca. Cl. Plug down at 9:05 p.m. 8-17-76.

T.D. 4115'. First Plug was set at 1100' with 70 sx., 2nd plug set at 250' with 20 sx., 40' bridge with 10 sx., 50/50 posmix, 6% gel. Plug was down at 1:00 a.m. 8-27-76. State Plugger Gilbert Balthazor, Palco, Kansas.

SAMPLE TOPS:

Anhydrite 2224' (+362)
 B/Anhydrite 2258' (+328)

RECEIVED
 STATE CORPORATION COMMISSION

SEP 02 1976

CONSERVATION DIVISION
 Wichita, Kansas


STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jerry A. Langrehr, Executive Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the MARTIN #1, NW SW NE, Section 16-10S-26W, Sheridan County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jerry A. Langrehr
 Jerry A. Langrehr, Exec. V. P.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 31st day of August, 1976.



COPY

Sandra Richman
 Sandra Richman, Notary Public