

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-179-21045-0000

LEASE NAME Tilton

WELL NUMBER 16-11

1650 Ft. from S Section Line

3560 Ft. from E Section Line

SEC. 16 TWP. 10S RGE. 26 (X) or (W)

COUNTY Sheridan

Date Well Completed 9/29/92

Plugging Commenced 9/29/92

Plugging Completed 9/29/92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR L. B. Industries, Inc. 80112

ADDRESS 12200 E. Briarwood Ave., Suite 250, Englewood CO

PHONE# (303) 790-8340 OPERATORS LICENSE NO. 3680

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 29, 1992 (date)

by Marvin Miller (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation NA Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		Surface	336	8-5/8"	336'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Hole was full of 9-2 ppg mud, plugs spotted by DP displacement. Used 60-40 Pozmix + 6% gel + 1/4 lb Flocele/sack. Plug #1, 25 sx, from 2230' to 2110', plug #2, 100 sx, from 1310' to 844', plug #3, 40 sx, from 375' to 189', plug #4, 10 sx @ 40' to surface. 15 sx in rat hole and 10 sx in mouse hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Chief Drilling, Inc. License No. 5886

Address 120 S. Market, #300, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L. B. Industries, Inc.

STATE OF Colorado COUNTY OF Arapahoe, ss.

Layle L. Robb (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Layle L. Robb

(Address) 12200 E. Briarwood Ave., Suite 250 Englewood, CO 80112-6702

SUBSCRIBED AND SWORN TO before me this 6th day of October, 19 92

Peggy Steffin
Notary Public Peggy Steffin

KCC Commission Expires: 8/11/96



RECEIVED
STATE CORPORATION COMMISSION
10-8-92
OCT 8 1992
CONSERVATION DIVISION
Wichita, Kansas