

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-179-20,796-0000

LEASE NAME TILTON #16-12

WELL NUMBER #16-12

SPOT LOCATION NW NW SW

SEC. 16 TWP. 10 SRGE. 26 ~~EXXK~~(W)

COUNTY Sheridan

Date Well Completed 2-02-85

Plugging Commenced 2-2-85

Plugging Completed 2-2-85

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR L.B. Petroleum, Inc.

ADDRESS 370 17th St. Suite #3200

Denver, Colorado 80202

PHONE # (316) 262-3791 OPERATORS LICENSE NO. \_\_\_\_\_

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #6

Is ACO-1 filed? yes If not, is well log attached? yes

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4448'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
surface	7 jts. 259' 8"	5/8"	24#	set @ 262'	cem.	w/175 sx. 60-40
	posmic, 2% ge	, 3% c.c.				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged w/180 sx. 50-50 posmix, 6% gel, 3% c.c., 1st plug @ 2250'  
w/20 sx., 2nd plug @ 1350' w/100 sx., 1 sx. flowseal, 3rd plug @  
350' w/40 sx., 10 sx. in the rathole, started plugging @ 2:30 p.m.  
finished plugging @ 5:30 p.m. Gibb Lieker, Dist. #6 State Plugger  
(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Warrior Drilling Co. License No. 5883  
Address 905 Century Plaza, Wichita, KS. 67202

STATE OF Kansas COUNTY OF Sheridan, ss.

~~KOP EXXK~~ F.W. Shelton, Jr., (employee of operator) or  
of above-described well, being first duly sworn on oath, says: That  
I have knowledge of the facts, statements, and matters herein contained and  
the log of the above-described well is a true and correct copy of the same and  
correct, so help me God.

FEB 28 1985

(Signature) F.W. Shelton, Jr.

(Address) 905 Century Plaza  
Wichita, Ks. 67202

CONSERVATION DIVISION  
SUBSCRIBED AND SWORN TO before me this 5 day of Feb., 1985

MARTHA E. GUSTIN  
NOTARY PUBLIC  
STATE OF KANSAS

Martha E. Gustin  
Notary Public  
Martha E. Gustin

My Commission expires: 1-15-85

DRILLERS LOG

February 5, 1985

TILTON #16-12  
NW NW SW 16-10S-26W  
SHERIDAN COUNTY, KS.

OPERATOR: L.B. Petroleum  
CONTRACTOR: Warrior Drilling, Co. Rig #1  
COMMENCED: January 25, 1985  
COMPLETED: February 2, 1985

8 5/8" @ 262' w/175 sx.,

0	43	surface clay
43	658	sand & clay
658	2234	shale
2234	2276	anhydrite
2276	2465	shale
2465	3289	shale & lime
3289	3967	lime & shale
3967	4448	lime
4448'		RTD

D & A


We certify that the above and foregoing is a true and correct copy of the log on the Tilton #16-12, located in Sheridan Co., Kansas.

Warrior Drilling Co.


RECEIVED  
STATE CORPORATION COMMISSION

FEB 28 1985

CONSERVATION DIVISION  
Topeka, Kansas

  
F.W. Shelton, Jr.  
Vice President

Subscribed and sworn to before me this 4th day of February, 1985.

  
Martha E. Gustin Notary