

API NUMBER 15-195-22,144-00-00

LEASE NAME Toto

WELL NUMBER 8-4-5

330 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 5 TWP. 12 RGE. 25 (E) or (W)

COUNTY Trego

Date Well Completed 9/17/94

Plugging Commenced 9/17/94

Plugging Completed 9/17/94

*Rec'd  
 09-21-1994*

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Diversified Operating Corporation

ADDRESS 1675 Larimer Street, Suite #850, Denver, CO

80202-1523

PHONE# (303) -595-3957 OPERATORS LICENSE NO. 31016

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/17/94 (date)

by David Wann (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 4660'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	248'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Mud laden fluid 4660'-4575' 40 sks cement @ 290'  
25 sks cement @ 4575' 10 sks cement @ 40'  
25 sks cement @ 2100' 10 sks cement in Mousehole  
100 sks cement @ 1150' 15 sks cement in Rathole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Diversified Operating Corporation


STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
Kyle B. Branum

(Address) Box 506, Russell, KS 67665-0506

SUBSCRIBED AND SWORN TO before me this 19th day of September, 1994



Glenda R. Tiffin  
 Glenda R. Tiffin, Notary Public

Commission Expires: 2-6-96

EMPHASIS OIL OPERATIONS  
A Division of N-B Company, Inc.  
P. O. BOX 506  
RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Diversified Operating Corporation  
1675 Larimer Street, Suite #850  
Denver, Colorado 80202-1523

CONTRACTOR: Emphasis Oil Operations  
Box 506  
Russell, KS 67665

LEASE: Toto WELL #8-4-5 LOCATION: NW NW NW  
Section 5-12S-25W  
Trego County, Kansas

LOGGERS TOTAL DEPTH: 4665'  
ROTARY TOTAL DEPTH: 4660'  
COMMENCED: 9/9/94  
CASING: 8-5/8" @ 248' w/145 sks cement

ELEVATION: 4660' K.B.  
COMPLETED: 9/17/ 94  
STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Shale	165'	Lime & Shale	3461'
Shale & Sand	1394'	Shale & Lime	4058'
Anhydrite	2092'	Lime & Shale	4122'
Shale & Lime	2132'	Shale & Lime Sand	4306'
Lime & Shale	2851'	Lime & Shale (Arbuckle)	4585'
Shale & Lime	3273'	R.T.D.	4660'


STATE OF KANSAS )  
                  ) ss  
COUNTY OF RUSSELL)

Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

  
\_\_\_\_\_  
Kyle B. Branum

Subscribed and sworn to before me on September, 19, 1994.

My commission expires: February 6, 1996.

STATE  
  
\_\_\_\_\_  
Glenda R. Tiffin, Notary Public

09-21-1994  
SEP 21 1994