

15-195-00498-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Trego County, Sec. 25 Twp. 12 Rge 25 (E) (WPC)
Location as "NE/CNW/SW" or footage from lines. C NE NE
Lease Owner James F. Zeman
Lease Name Jagger Well No. 1
Office Address Hays, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D. & A.
Date well completed 12/17/63 19
Application for plugging filed 12/17/63 19
Application for plugging approved 12/17/63 19
Plugging commenced 12/17/63 19
Plugging completed 12/17/63 19
Reason for abandonment of well or producing formation -0-

If a producing well is abandoned, date of last production -0- 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation -0- Depth to top -0- Bottom -0- Total Depth of Well 4650' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	236'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Rotary mud was used to fill hole to a depth of 600' were 1st plug was set using 20 sacks cement, filling hole to a depth of 220' were 2nd plug was set using 20 sacks cement, filling hole to a depth of 40' were 3rd plug was set using 10 sacks cement and filling hole to surface.

RECEIVED
STATE CORPORATION COMMISSION

DEC 30 1963
15-30-1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. DRETLING & SONS, INC.
Address VICTORIA, KANSAS

STATE OF KANSAS, COUNTY OF ELLIS, ss.

I, Leo F. Dreiling, a contractor (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling

(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of December, 1963

Armond Zimmerman
Notary Public.

My commission expires August 14, 1965

15-195-00498-00-00

L. J. DREILING and SONS, Inc.
VICTORIA, KANSAS

WELL LOG

Company James F. Zeman

Sec. 25 Twp. 12S Rng. 25W

Farm Jagger No. 1

Location 6 NW 1/4 NE NE

Total Depth 4650'

County Trego County

Comm. 12/6/63 Comp. 12/17/63

Elevation: D. F. 2448'

Contractor L. J. DREILING & SONS, INC.
VICTORIA, KANSAS

G. R. 2446'

Casing Record
236' - - - 8 5/8"

Cement Record
135 sacks cement

Production:
D. & A.

Figures Indicate Bottom of Formations

0 - 50	Surface Clay
50 - 236	Sand & Shale
236 - 750	Shale
750 - 880	Sand
880 - 981	Shale
981 - 1400	Shale & Sand
1400 - 1529	Shale
1529 - 1780	Sand
1780 - 2030	Red Bed
2030 - 2072	Anhydrite
2072 - 2075	Shale
2075 - 2405	Shale
2405 - 2592	Shale & Lime
2592 - 2725	Shale & Shells
2725 - 2816	Lime
2816 - 2947	Lime
2947 - 3077	Shale & Lime
3077 - 3215	Shale
3215 - 3300	Lime
3300 - 3460	Shale & Lime
3460 - 3608	Lime
3608 - 3775	Lime
3775 - 3845	Lime
3845 - 3862	Lime
3862 - 3973	Lime
3973 - 4049	Lime
4049 - 4130	Lime
4130 - 4175	Lime
4175 - 4275	Lime
4275 - 4335	Lime
4335 - 4403	Lime
4403 - 4483	Lime
4483 - 4530	Lime
4530 - 4530	Lime
4530 - 4615	Lime
4615 - 4650	Lime
4650	TD

RECEIVED
STATE CORPORATION COMMISSION
DEC 30 1963
12-30-1963
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS }
 } ss.
COUNTY OF HILLIS }

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report on your Jagger No. 1.

Leo F. Dreiling
LEO F. DREILING

Subscribed and sworn to before me this 23rd day of December, 1963.

Ronald Zimmerman
NOTARY PUBLIC

My Commission Expires: August 14, 1965