


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Gove County, Sec. 17 Twp. 12 Rge. 26 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner Francis Oil & Gas Inc.
Lease Name 905 Palace Building Martha Jameson ^{Jamison AUB KCC} Well No. 1
Office Address Tulsa, Oklahoma - 905 Palace Building
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-31-58 19
Application for plugging filed 5-31-58 19
Application for plugging approved 5-31-58 19
Plugging commenced 5-31-58 19
Plugging completed 5-31-58 19
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. A. Lieker, Victoria, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4218 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	230' W/135 sacks	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug at 500' w/20 sacks cement.
Mud to 180'
Set plug w/1/2 sack hulls 20 sacks cement.
Mud to 40'
Set plug with 1/2 sack hulls
Cemented to bottom of cellar

06-10-1958

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Veeder Supply and Development Company
Address Box 201, Cherryvale, Kansas

STATE OF Kansas, COUNTY OF Montgomery, ss.
C. H. Woods (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. H. Woods

Cherryvale, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of June, 19 58

Walter Lawson

Notary Public.

My commission expires July 11, 1960.

PLUGGING
FILE SEC 17 T. 12 R. 26
BOOK PAGE 104 LINE 30

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Francis Oil & Gas Inc., Herman Geo. Kaiser
 Drilled for Veeder Supply & Development Co. Farm Martha Jameson No. 1 Depth 4218'
 Contractor Veeder Supply & Development Co. Pipe 230' 8 5/8" csg. w/135 sacks
 Location NENE NE Sec. 17 Twp. 12 Range 26
 Commenced 5-22-1958 Completed 5-31-1958 County Gove State Kansas

Elevation: 2628' DF

Soil	0	40	40	TOPS:	
Sand, Gravel, Shale	40	128	88	Heebner	3916
Shale	128	230	102	Toronto	3938
Shale, shells	230	1100	870	Lansing KC	3955
Sand	1100	1470	370		
Shale and shells	1470	1825	355		
Sand and shale	1825	2010	185		
Shale w/sand streaks	2010	2163	153		
Shale, shells, red bed	2163	2228	65		
Anhydrite	2228	2275	47		
Shale shells	2275	2630	355		
Shale	2630	2655	25		
Lime and shale streaks	2655	2775	120		
Lime and shale	2775	3645	870		
Shale lime	3645	3735	90		
Lime	3735	4218	483		
T. D.	4218				

D&A

AFFIDAVIT

STATE OF KANSAS)
Montgomery County) SS

C/ H. Woods, of lawful age, being first duly sworn on oath, deposes and says:

THAT he has read the above drilling log covering the Martha Jameson #1 well located in Section 17-12-26, Gove County, Kansas, and that the same is true and correct. Further affiant saith not.

THE VEEDER SUPPLY AND DEVELOPMENT CO.

By C. H. Woods
C. H. Woods

Subscribed and sworn to before me this 4th day of June, 1958.

Colin Lawson
Notary Public

My commission expires July 11, 1960.



JUN 10 1958
06-10-1958

PLUGGING
 FILE SEC. 17 T. 12 R. 26 W
 BOOK PAGE 104 LINE 30