

1090957

TO: STATE CORPORATION COMMISSION 10-8

API NUMBER 15-033-20,775
NW NW ~~NW~~ SEC. 35, T 34 S, R 20 W
SW AUB KCC

CONSERVATION DIVISION - PLUGGING SECTION 2300 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME BAKER WELL # 1-35

TECHNICIAN'S PLUGGING REPORT COUNTY COMANCHE 212.07

OPERATOR LICENSE # 4145 WELL TOTAL DEPTH 6525 FEET

OPERATOR: ROBERTS & MURPHY, INC PRODUCTION CSG: SIZE 4 1/2 " FEET 6420

NAME AND PO BOX 7125 SURFACE CASING: SIZE 8 5/8 " FEET 653'

ADDRESS SHREVEPORT, LA 71137-7125

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR PRATT WELL SERVICE LICENSE NUMBER 5893

ADDRESS PO BOX 847, PRATT, KS 67124

COMPANY TO PLUG AT: HOUR: 10:15 AM DAY: 08 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM KEN FRAZIER

(COMPANY NAME) PRATT WELL SERVICE (PHONE) 316-672-5901

WERE: PERFS AT 6268-76

SET CIBP AT 6000' AND DUMP BAIL 2 SX CEMENT. CUT CASING AND PULL. PUMP FROM SURFACE
50 SX CEMENT, 8 5/8" PLUG AND 100 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 11:00 AM DAY: 08 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT

SET CIBP AT 6000' WITH 2 SX CEMENT ON TOP.

1ST PLUG PUMP IN 8 5/8" CASING 3 HULLS, 10 GEL, 50 SX CEMENT, 10 GEL, 1 HULL AND 150 SX
CEMENT. MAXIMUM PSI PRESSURE 500#. SHUT IN AT 400#.

REMARKS: 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3028' OF 4 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID)OBSERVE THIS PLUGGING.

SIGNED (TECHNICIAN) FORM CP-2/3

10-19-98
60127

10-14-1998
STATE CORPORATION COMMISSION
RECEIVED
10 12