

API NUMBER 15- 033-20,900

To: 1 051890 1-22
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

App. N/2 SW SW, SEC. 35, T 34 S, R 20 W/E

950 feet from S section line
660 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4145
Operator: Roberts & Murphy, Inc.
Name & Address: P.O. Box 7125
Shreveport, LA 71137

Lease Name Baker Well # 3-35
County Comanche
Well Total Depth 6500 211.25 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 643

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Eagle Drilling License Number 5380

Address 110 N. Market, Ste. 411, Wichita, KS 67202

Company to plug at: Hour: 8 a.m. Day: 22 Month: 1 Year: 1995

Plugging proposal received from Butch Steinert

(company name) Eagle Drilling (phone) 316-265-1072

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 850' with 40 sx cement, 2nd plug at 660' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:45 a.m. Day: 22 Month: 1 Year: 1995

ACTUAL PLUGGING REPORT 1st plug at 850' with 40 sx cement,

2nd plug at 660' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

() () () did not observe this plugging.

INVOICED
DATE 2-8-95

INV. NO. 42182

Signed Richard W. Lacey (TECHNICIAN)

