

1090956

TO: STATE CORPORATION COMMISSION

10-8

API NUMBER 15-033-20,774
SW SE SEC. 27, T 34 S, R 20 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2300 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME PETTY WELL # 1-27

TECHNICIAN'S PLUGGING REPORT

COUNTY COMANCHE 211.25

OPERATOR LICENSE # 4145

WELL TOTAL DEPTH 6500 FEET

OPERATOR: ROBERTS & MURPHY, INC

PRODUCTION CSG: SIZE 4 1/2 " FEET 6500

NAME AND ADDRESS PO BOX 7125 SHREVEPORT, LA 71137-7125

SURFACE CASING: SIZE 8 5/8 " FEET 651'

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR PRATT WELL SERVICE LICENSE NUMBER 5893

ADDRESS PO BOX 847, PRATT, KS 67124

COMPANY TO PLUG AT: HOUR: 2:00 PM DAY: 08 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM KEN FRAZIER

(COMPANY NAME) PRATT WELL SERVICE (PHONE) 316-672-5901

WERE: PERFS AT 5012-21

SET CIBP AT 5000' AND DUMP BAIL 2 SX CEMENT. CUT CASING AND PULL. PUMP FROM SURFACE 50 SX CEMENT, 8 5/8" PLUG AND 100 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 2:35 PM DAY: 08 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT

SET CIBP AT 4975' WITH 2 SX CEMENT ON TOP.

1ST PLUG PUMP IN 8 5/8" CASING 3 HULLS, 10 GEL, 50 SX CEMENT, 10 GEL, 1 HULL AND 150 SX CEMENT. MAXIMUM PSI PRESSURE 500#. SHUT IN AT 150#.

REMARKS: 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3300' OF 4 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED [Signature] (TECHNICIAN) FORM CP-2/3

10-19-98
60126

MSAS
10-11-1998
12:12