

To: 1 090241 12-22 15-033-20781-00-00  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION SW NW SE NE, SEC. 28, T. 34 S, R. 20 W EX  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202 3580 feet from S section line

TECHNICIAN'S PLUGGING REPORT 1250 feet from E section line

Operator License # 4145 Lease Name Miller Well # 1-28

Operator: Roberts & Murphy, Inc. County Comanche 223.73

Name & Address P.O. Box 7125 Well Total Depth 6884 feet

Shreveport, LA 71137-7125 Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 665

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 9:30 a.m. Day: 22 Month: 12 Year: 19 92

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service (phone) 316-672-5901

were: 4 1/2" at 5528' w/200 sx cement, PBTD 5474', Perfs at 5330-32'

1st plug set CIBP at 5250' and dump 2 sx cement on top,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:45 a.m. Day: 22 Month: 12 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5250' and dumped 2 sx cement on top,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"  
wiper plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 4880' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

(old, ~~do not~~) observe this plugging.

DATE 1-8-93

INV. NO. 37160

Signed [Signature]  
(TECHNICIAN)

12-14-92