

15-033-20561-00-00

1 080276

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-033-20,561
NE NE, SEC. 26, T 34 S, R 20 W/E

4620 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6420

Lease Name Lemon Well # 1-26

Operator: K.R.M. Petroleum Corp.

County Comanche 170.30

Name & Address 1900 Grant Street, Suite 300

Well Total Depth 5240 feet

Denver, CO 80203

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 670

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: noon Day: 5 Month: December Year: 19 84

Plugging proposal received from Norman Voth

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" set at 4856' PBD 4854' Perfs at 4794-4800'

1st plug pump 45 sx cement to bottom and set plug at 4500' (Common cement 3% cc)

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pump 125 sx cement.

RECEIVED
12-12-1984
DEC 12 1984

Plugging Proposal Received by J. H. Metz
Wichita, Kansas
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 pm Day: 5 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 4856' PBD 4854' Perfs at 4794-4800'

1st plug pumped 45 sx cement to bottom and set plug at 4500', 2nd plug squeezed well with

3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber

plug and pumped an additional 125 sx cement.

Maximum pressure 800 psi and shut in 400 psi

Remarks: Recovered 3800' 5 1/2" casing. Used Common cement with 3% cc and 60/40 Pozmix
(If additional description is necessary, use BACK of this form.)

12-20-84
DATE (did / did not) observe this plugging.

INV. NO. 6071

Signed J. H. Metz
(TECHNICIAN)